

Annual Surmont SAGD Performance Review Approval 9426

April 24, 2019

Calgary, Alberta, Canada

Table of Contents – AER Scheme Approval No. 9426

Subsurface

- Subsection 3.1.1 (1): Introduction, Overview and Highlights – 3
- Subsection 3.1.1 (2): Geology & Geoscience - 7
- Subsection 3.1.1 (3): Drilling & Completions - 41
- Subsection 3.1.1 (4): Artificial Lift – 55
- Subsection 3.1.1 (5): Instrumentation in Wells – 60
- Subsection 3.1.1 (6): 4D Seismic – 66
- Subsection 3.1.1 (7): Scheme Performance – 76
- Subsection 3.1.1 (8): Future Plans – 106

Surface

- Subsection 3.1.2 (1): Facilities Introduction – 108
- Subsection 3.1.2 (2): Facility Performance – 128
- Subsection 3.1.2 (3): MARP – 144
- Subsection 3.1.2 (4): Water Production, Injection & Disposal – 154
- Subsection 3.1.2 (5): Sulphur Production – 170
- Subsection 3.1.2 (6): Environmental Compliance – 176
- Subsection 3.1.2 (7 & 8): Compliance Confirmation and Noncompliance – 180
- Subsection 3.1.2 (9): Future Plans – 183

Introduction, Overview and Highlights

Subsection 3.1.1 (1)

Ownership and Approvals

► Ownership

- The Surmont In-Situ Oil Sands Project is a 50/50 joint venture between ConocoPhillips Canada Resources Corp. (ConocoPhillips) and TOTAL E&P Canada Ltd; operated by ConocoPhillips.

► Project History

- 1997 - First steam at pilot project
- 2007 - First steam at Phase 1
- 2010 - Construction start at Phase 2
- 2015 - Start-up of Phase 2

► Approval Update - AER Approval No. 9426

Approval 9426NN – February 1, 2018

- Application No. 1902010 – NCG Co-injection at four Phase 1 DAs and eleven Phase 2 DAs
- Application No. 1903163 – MOP increase at six Phase 2 DAs: 266-2, 263-2, 264-2, 263-1, 264-1, and 103

Approval 9426OO – March 23, 2018

- Application No. 1906715 – Alternate diluent project to enable the use of condensate

Approval 9426PP – October 9, 2018

- Application No. 1913016 – Addition of eight cooled heat exchanges at the S2 CPF in support of the alternate diluent project

Surmont Overview


Phase 1 is focused on the optimization of production and steam

Phase 2 is focused on the well ramp up and pressure management

Currently in a “One Surmont” philosophy


Surmont combined approved capacity is 29,964 m³/cd (188,700 bbl/cd)*

***(where cd is calendar day on an annual average basis)**




Surmont Performance

Historical Steam Injection and Bitumen Production



iSOR vs Time



2018 Highlights

Phase 1 production recovery

- Continued execution of Pad 102S NCG Pilot.
- Managing pressures in Pad 103 to mitigate coalescence issues between DA's.
- iSOR as of February 28, 2019 is at an average 2.99.

Phase 2 continued ramp-up


- Continuous evaluation of pressure strategies among DA's to optimize SOR.
- Thirty-seven ESP conversions performed, enabling implementation of pressure strategy.
- Focus in understanding underperformance of specific areas within Surmont 2.
- Started NCG pilot for mitigation of thief zone issues.
- iSOR as of February 28, 2019 is at an average of 2.96.

Subsurface Resource Evaluation and Recovery

Geology and Geoscience

Subsection 3.1.1 (2)



OBIP Volumes: Reservoir Properties of Development Area



Surmont Development Area OBIP


$$\text{OBIP} = \text{Thickness} \times \text{Phie} \times \text{So} \times \text{Area}$$

OBIP Volumes: Reservoir Properties Operating Portion



| Properties | Depth (masl) | Area (m2) | Thickness NCB (m) | Phie in NCB % | So in NCB % | KH in NCB (mD) | KV in NCB (mD) | Initial Pressure (KPa) |
|------------|-----------------|-----------|-------------------|---------------|-------------|----------------|----------------|------------------------|
| Lease | ~250 | 578578000 | 23.07 | 31.82% | 76.79% | 4113 | 3423 | 1700 |
| 101N | 277.52 - 212.11 | 1090775 | 35.53 | 32.58% | 82.40% | 4350 | 3614 | 1690 |
| 101S | 272.96 - 218.47 | 1064692 | 37.43 | 33.19% | 80.41% | 5482 | 4604 | 1684 |
| 102N | 276.39 - 223.91 | 975251 | 31.14 | 32.71% | 80.29% | 4636 | 3877 | 1735 |
| 102S | 285.02 - 223.61 | 1019252 | 34.17 | 31.32% | 74.33% | 4001 | 3290 | 1800 |
| 103 | 272.82 - 211.40 | 1022239 | 42.80 | 32.21% | 78.62% | 4441 | 3691 | 1691 |
| 261-3 | 271.02 - 201.80 | 1000542 | 44.77 | 32.00% | 78.07% | 4342 | 3562 | 1328 |
| 262-1 | 273.64 - 206.15 | 996252 | 39.59 | 31.74% | 80.05% | 4195 | 3471 | 1307 |
| 262-2 | 271.89 - 212.60 | 974291 | 38.63 | 33.13% | 78.56% | 5239 | 4420 | 1296 |
| 262-3 | 271.57 - 208.64 | 943213 | 44.28 | 32.76% | 78.21% | 4968 | 4140 | 1368 |
| 263-1 | 272.12 - 211 | 1271315 | 36.14 | 32.98% | 79.36% | 4966 | 4170 | 1404 |
| 263-2 | 275.41 - 212.90 | 998219 | 40.90 | 32.44% | 78.06% | 4769 | 3979 | 1397 |
| 264-1 | 271.18 - 213.54 | 1033834 | 39.45 | 32.89% | 79.71% | 5148 | 4338 | 1444 |
| 264-2 | 269.27 - 213.75 | 1011337 | 42.08 | 32.65% | 78.22% | 4763 | 3965 | 1437 |
| 264-3 | 281.29 - 207.61 | 1209485 | 37.51 | 31.97% | 75.58% | 4446 | 3683 | 1564 |
| 265-2 | 271.50 - 215.59 | 917433 | 38.75 | 32.54% | 76.83% | 4917 | 4101 | 1496 |
| 266-2 | 276.26 - 210.21 | 949974 | 42.99 | 32.83% | 80.08% | 4925 | 4121 | 1337 |

McMurray Gross Isopach





McMurray Gross Isopach

2018/2019 Mapping Update

- No delineation/no changes

McMurray Net Gas Isopach





Net Top Gas thickness =
sands have deep resistivity
 $\geq 10 \Omega\text{-m}$ and $V_{sh} < 65\%$

McMurray Net Gas Isopach


2018/2019 Mapping Update

- No delineation/no changes

McMurray Net Top Water Isopach



Surmont Lease



Development Area



Drainage Areas



Net Top Water thickness =
sands have deep resistivity
<10 Ω -m and Vsh <45%

McMurray Net Top Water Isopach


2018/2019 Mapping Update

- No delineation/no changes


McMurray Net Bottom Water Isopach



Surmont Lease



Development Area



Drainage Areas


Net Bottom Water thickness =
sands have deep resistivity
<10 Ω -m and Vsh <45%

McMurray Net Bottom Water Isopach

2018/2019 Mapping Update

- No delineation/no changes

McMurray Top Continuous Bitumen Structure





TCB = The uppermost limit of good reservoir, bitumen-bearing sands.

Top Continuous Bitumen Structure


2018/2019 Mapping Update

- No delineation/no changes

McMurray Base Continuous Bitumen Structure



Surmont Lease



Development Area



Drainage Areas


BCB = First occurrence of good reservoir, bitumen- bearing sands.

Base Continuous Bitumen Structure

2018/2019 Mapping Update

- No delineation/no changes

McMurray Net Continuous Bitumen Thickness




Net continuous bitumen =
sands have deep resistivity
> 40 Ω -m and Vsh <33%,
and no shale greater
than 3 m thick

McMurray Net Continuous Bitumen Pay

2018/2019 Mapping Update

- No delineation/no changes

INTERPRETING SAGD INTERVAL



Fluid Surfaces

- Top Gas Surface:** The uppermost limit of gas-bearing sands
- Bottom Gas Surface:** The lowest occurrence of gas-bearing sands
- Top Water Surface:** The uppermost limit of water-bearing sands
- Bottom Top Water Surface:** The lowest occurrence of water-bearing sands above the bitumen
- Top Bitumen Surface:** The uppermost limit of bitumen-bearing sands with deep resistivity of 10 ohm or greater and a Vsh cutoff of less than 33%
- Top Continuous Bitumen Surface (TCB):** The uppermost limit of good reservoir, bitumen-bearing sands.
- Base Continuous Bitumen Surface (BCB):** The first occurrence of good reservoir, bitumen-bearing sands with deep resistivity of 40 ohmm or greater, or 8wt% bitumen.
- Base Bitumen Surface:** The lowest occurrence of bitumen-bearing sands with deep resistivity of 10 ohm or greater and a Vsh cutoff of less than 33%
- Top Bottom Water Surface:** The uppermost limit of water-bearing sands below bitumen
- Bottom Water Surface:** The lowest occurrence of water-bearing sands below the bitumen

Gross Fluids

Top Gas: Gross thickness of gas-bearing sands defined by the top and bottom gas surfaces


Top Water: Gross thickness of water-bearing sands defined by the top and bottom water surfaces

Continuous Bitumen / SAGD Interval
Gross thickness of continuous bitumen reservoir with deep resistivity of 40 ohmm or greater, and does not include continuous muds greater than 3m thick. SAGD interval would be from the producer level (approx. 5m above BCB) to the top of this zone.

Bitumen: Gross thickness of bitumen-bearing sands defined by the top and base bitumen surfaces

Bottom Water: Gross thickness of water-bearing sands defined by the top and bottom water surfaces

Phase 1 Type Log Well Pad 101



Example Log 100161408307W400



McMurray

High Sw

Continuous
Bitumen


High Sw

Devonian



Phase 1 Area

Phase 2 Type Log – Well Pad 264-2





Example Log 100162208306W400

McMurray
Top Gas

High Sw

Continuous
Bitumen

Devonian




Type Log

Phase 2 Area

Phase 2 Type Log – Well Pad 261-3

Example Log 100043508306W400




| Tops Description | |
|------------------|----------------------------------|
| WBSK | Wabiskaw Member |
| WBSK_MKR | Wabiskaw Marker |
| MCMR | McMurray Formation |
| MCMR_TB | McMurray Top Bitumen |
| MCMR_TCB | McMurray Top Continuous Bitumen |
| MCMR_BCB | McMurray Base Continuous Bitumen |
| MCMR_BB | McMurray Base Bitumen |
| pre_K | Pre-Cretaceous Unconformity |

| Name | Pattern |
|----------------------------|-----------|
| Coarse sand | [Pattern] |
| Medium sand | [Pattern] |
| Fine sand | [Pattern] |
| Sandy IHS | [Pattern] |
| Muddy IHS | [Pattern] |
| Mudstone | [Pattern] |
| Carbonate | [Pattern] |
| Breccia | [Pattern] |
| Coal | [Pattern] |
| Cemented | [Pattern] |
| Till | [Pattern] |
| Rafted Till | [Pattern] |
| Interbedded Sand_Mud | [Pattern] |
| Bioclastic Sand & Mudstone | [Pattern] |


Continuous Bitumen

Phase 2 Area

McMurray Net Continuous Bitumen (NCB)




Example Log



Drainage Area

Phase 2 Type Log – Well Pad 262-2

Example Log 100163408306W400




| Name | Pattern |
|-----------------------------|---------|
| Coarse sand | |
| Medium sand | |
| Fine sand | |
| Sandy IHS | |
| Muddy IHS | |
| Mudstone | |
| Carbonate | |
| Breccia | |
| Coal | |
| Cemented | |
| Till | |
| Rafted Till | |
| Interbedded Sand_Mud | |
| Bioturbated Sand & Mudstone | |

Continuous Bitumen

| Tops Description |
|----------------------------------|
| WBSK |
| Wabiskaw Member |
| WBSK_MKR |
| Wabiskaw Marker |
| MCMR |
| McMurray Formation |
| MCMR_TB |
| McMurray Top Bitumen |
| MCMR_TCB |
| McMurray Top Continuous Bitumen |
| MCMR_BCB |
| McMurray Base Continuous Bitumen |
| MCMR_BB |
| McMurray Base Bitumen |
| pre_K |
| Pre-Cretaceous Unconformity |


Phase 2 Area



Drainage Area

Phase 1 Type Log – Well Pad 103

Example Log 100052308307W400




| Tops Description |
|----------------------------------|
| WBSK |
| Wabiskaw Member |
| WBSK_MKR |
| Wabiskaw Marker |
| MCMR |
| McMurray Formation |
| MCMR_TB |
| McMurray Top Bitumen |
| MCMR_TCB |
| McMurray Top Continuous Bitumen |
| MCMR_BCB |
| McMurray Base Continuous Bitumen |
| MCMR_BB |
| McMurray Base Bitumen |
| pre_K |
| Pre-Cretaceous Unconformity |

| Name | Pattern |
|-----------------------------|-----------|
| Coarse sand | [Pattern] |
| Medium sand | [Pattern] |
| Fine sand | [Pattern] |
| Sandy IHS | [Pattern] |
| Muddy IHS | [Pattern] |
| Mudstone | [Pattern] |
| Carbonate | [Pattern] |
| Breccia | [Pattern] |
| Coal | [Pattern] |
| Cemented | [Pattern] |
| Till | [Pattern] |
| Rafted Till | [Pattern] |
| Interbedded Sand_Mud | [Pattern] |
| Bioturbated Sand & Mudstone | [Pattern] |

Continuous Bitumen



Phase 1 Area




Drainage Area

Well Pad 262-1 Variable Bitumen-Water Contact


- A well at 4-3-84-6 W4M intersected a raised bitumen/water contact, the contact is ~ 12 m higher than the nearest offset.
- The well also intersected a small gas pool under the bitumen.
- The presence of basal water becomes a potential impact on production performance on Well Pad 262-1



2018-2019 Delineation Campaign and Well Density




Surmont Lease as of March 1, 2019




**No new wells were drilled between
Mar 1, 2018 to Mar 1, 2019**

2018-2019 Delineation Campaign and Core Density




Surmont Lease as of March 1, 2019

- 1531 wells total
- 549 existing core wells
- Phase 1 and Phase 2 Development Area
- Drainage Areas



No new cores were cut between
Mar 1, 2018 to Mar 1, 2019

2018-2019 Delineation Campaign and FMI/CMI Logs



Surmont Lease as of March 1, 2019


- 1531 wells total
- 1154 existing FMI/CMI wells
- Phase 1 and Phase 2 Development Area
- Drainage Areas
- Surmont lease

No new wells were drilled between March 1, 2018 and March 1, 2019; hence no FMI/CMI logs were taken


2018-2019 Delineation Campaign and Well Density

Delineation across Phases 1, 2, and 3


Delineation Well Density Map Mar 2018



Delineation Well Density Map Mar 2019



Density Map Difference




McMurray
penetrated
wells only


2018-2019 Delineation Campaign and Well Density

Increased core density with latest drilling


Cored Wells Density Map Mar 2018



Cored Wells Density Map Mar 2019



Cored Density Map Difference




McMurray
penetrated
wells only


2018-2019 Delineation Campaign and Well Density

Increased Formation Micro Imaging density with latest drilling


FMI Well Log Density Map
Mar – 2018



FMI Well Log Density Map
Mar - 2019



FMI Density Map Difference



McMurray
penetrated
wells only

Special Core Analyses Bitumen Viscosity Sampling

- **Objectives:**


- Characterize vertical and lateral variance in viscosity at different temperatures.
- Model the variance in bitumen properties and its implications for bitumen production rates during SAGD.
- Characterize relationship between viscosity, density and geochemical composition.

Viscosity increases with depth in the McMurray Formation.


● **52 existing viscosity sample wells**

● **Delineated Wells - Surmont**


No changes In 2018



Viscosity Gradient



Representative Structural Cross Section




Geomechanical Data and Analysis

- The existing DFIT and caprock core testing results are believed to provide the critical data required for caprock integrity analysis, in combination with other well and seismic data. Therefore, no additional DFITs or core testing was complete.
- Future caprock coring or DFITs may be planned as CPC investigates the caprock for new development of Surmont.
- The dilation pilot results are being further investigated and modifications might be considered for future trials.


Surface Deformation Monitoring

- Satellite (RADARSAT-2) measurements every 24 days
- Interferometric Synthetic Aperture Radar (InSAR):
 - Corner Reflectors (CR) installed over pads and in areas to measure background deformations.
 - 256 CR's installed since monitoring program began in 2008.
 - An additional 20 Corner reflectors were installed in 2017 at Phase 2 but are not tied into our current routine data collection yet, so they are not shown on the map.

Phase 1 Monitoring Locations





Phase 2 Monitoring Locations





InSAR Surface Deformation Monitoring

**Vertical Deformation (mm) for period
Feb 28, 2018 to Feb 28, 2019
(Surmont 1)**




**Vertical Deformation (mm) for period
Feb 28, 2018 to Feb 28, 2019
(Surmont 2)**



- Corner Reflector
- Reference Corner Reflector
- ◇ Corner Reflector w/quality issue
- ⊠ Corner Reflector w/Frost Jacking

- Deformation currently in line with expectations.

3D Seismic Lines




No changes In 2018

2012-2013 Seismic

| 3D | Km ² | Shots | S-R Line | S-R |
|-----|-----------------|--------|----------|-------|
| 103 | 1.9 | 1,700 | 60x80 | 20x20 |
| 104 | 2.9 | 1,103 | 60x80 | 20x20 |
| KW | 58.2 | 24,690 | 120X80 | 20X20 |
| KNW | 21.5 | 9,543 | 120x80 | 20x20 |

Caprock Integrity


- Caprock Core Analysis
 - 14 caprock cores were drilled and analyzed in 2015-2017.
 - Four rock mechanics testing programs were conducted in 2015-2017.
- Diagnostic Fracture Injectivity Tests (DFITs):
 - 8 DFITs were carried out in 2015-2017
 - DFIT locations were selected based on structural and geomechanical analysis of the caprock.
- Static Geomechanical Model
 - A static geomechanical model was created using all seismic, cores and wells data
 - The model is used for caprock integrity screening and analysis
 - The static geomechanical model of the reservoir and caprock was last updated in 2019Q1.
- The completed analysis verified that
 - The best seals within the cap rock interval are the deeper water deposits occurring on maximum flooding surfaces.
 - The seal over the development area is continuous, consistent and laterally extensive.



Caprock Integrity Analysis and Maximum Operating Pressure


- ConocoPhillips applies a highly conservative approach towards Subsurface Containment Assurance and follows a stringent approach based on internal SCA standards and regulations.
- Caprock integrity studies in ConocoPhillips include extensive geological, geophysical, petrophysical and geomechanical investigations. ConocoPhillips continues to acquire and interpret the data to mitigate SCA related risks.
- Results of caprock integrity studies allow ConocoPhillips to characterize and mitigate local risks related to geological and geomechanical variations. Analysis of caprock in the development area suggests while the previously used value of 18.4 kPa/m is valid, the minimum horizontal stress is higher in several drainage areas.
- ConocoPhillips continues to propose a flexible tapered strategy envelope bound by the cap rock integrity study and the associated Maximum Operating Pressure (MOP) on one side and economic achievable pressures on the other side. In 2017/18 temporary and permanent changes were made to the MOPs in a number of DAs in Surmont.
- ConocoPhillips has received approval to increase MOP from 15 kPa/m to 16.5 kPa/m in eight DAs in Surmont.
- Another approval was received to temporarily increase the MOP in one DA (262-3) to overcome near-wellbore barriers. A pilot test using one well pair was completed with the temporary MOP and results are being studied before proceeding with the rest of the DA well pairs.

Maximum Bottomhole Injection Pressure (kPag) – ALL PADs




Caprock Integrity Analysis and Maximum Operating Pressure

- The static geomechanical model used for caprock integrity analyses is regularly updated based on acquired and interpreted data.
- Static modeling of reservoir and caprock is used in combination with dynamic simulation of their geomechanical and pressure responses is used to estimate the SCA safety factors.
- For all applications and MOP changes, ConocoPhillips has demonstrated that the SCA safety factors have been maintained above 1.2 for the base cases.



Caprock Integrity Analysis Workflow





Surmont Development Area and Selected DAs for
MOP Increase (red outline)



Drilling and Completions

Subsection 3.1.1 (3)

Surmont Well Summary



Surmont FCD Installations




2018 Re-Drills


- Total of 15 re-drills in 2018.

| S1 Wells | Redrill Type | Justification |
|-----------|--------------|---|
| 101 P08 | Whipstock | Slotted liner failure |
| 101 P09 | Whipstock | Slotted liner failure |
| 102 P01 | Whipstock | Uplift, short production zone |
| S2 Wells | Redrill Type | Justification |
| 262-3 P03 | Whipstock | TDFCD liner failure |
| 262-3 P12 | Whipstock | Slotted liner failure |
| 263-1 I06 | Whipstock | Slotted liner failure |
| 263-1 P03 | Whipstock | Slotted liner failure |
| 263-1 P10 | Whipstock | Slotted liner failure |
| 263-2 P08 | Whipstock | SL failure and Intermediate casing damage |
| 264-2 P08 | Whipstock | Uplift, poor SL performance |
| 264-2 P10 | Whipstock | Slotted liner failure |
| 264-2 P11 | Open Hole | Uplift, poor SL performance |
| 264-3 P05 | Whipstock | Uplift, poor SL performance |
| 265-2 P01 | Whipstock | Slotted liner failure |
| 266-2 I04 | Whipstock | Plugged FCD liner; poor injectivity |


Typical Concentric Injector




Typical Parallel Injector




Improved Gas Lift Producer Design, 264-1




Improved Gas Lift Producer Design, 264-2, 263-2 & 263-1




Typical ESP Producer




Typical PCP Producer



Typical Liner Deployed Flow Control Device (LDFCD) Completion




Typical Tubing Deployed FCD (TDFCD) Completion – Gas Lift



| Pad | Total Wells with TDFCDs |
|-------|-------------------------|
| | Producer |
| 262-3 | 1 |
| 263-2 | 1 |


Typical Tubing Deployed FCD (TDFCD) Completion – ESP



| Pad | Total Wells with FCDs | |
|-------|-----------------------|-----------|
| | Producer | Injector* |
| 101 | 6 | 0 |
| 102 | 2 | 0 |
| 103 | 2 | 0 |
| 261-3 | 9 | 0 |
| 262-1 | 4 | 2 |
| 262-2 | 4 | 1 |
| 263-1 | 1 | 0 |
| 264-1 | 3 | 0 |
| 264-2 | 1 | 0 |
| 264-3 | 3 | 3 |
| 265-2 | 4 | 0 |

* Injector wells do not have instrumentation or GL coils

Current Surmont 2 Steam Splitter Design



Artificial Lift

Subsection 3.1.1 (4)

Artificial Lift Current Pad Overview

| | Phase 1 | | | Phase 2 | | | | | | | | | | | TOTAL |
|----------|---------|-----|-----|---------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| | 101 | 102 | 103 | 261-3 | 262-1 | 262-2 | 262-3 | 263-1 | 263-2 | 264-1 | 264-2 | 264-3 | 265-2 | 266-2 | |
| ESP | 20 | 18 | 11 | 12 | 12 | 12 | 0 | 11 | 3 | 7 | 2 | 12 | 12 | 12 | 144 |
| PCP | 2 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| Gas Lift | 0 | 0 | 1 | 0 | 0 | 0 | 12 | 0 | 8 | 5 | 9 | 0 | 0 | 0 | 35 |
| SSAGD | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Re-Circ. | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Circ. | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Artificial Lift Types

- **Gas Lift**
 - Gas lift is effective with bottom hole flowing pressures $>2,700$ kPa with pressure of well head (Pwh) approx. 1,000 kPa
 - Lifting from heel and toe with gas assist at start of vertical section
 - Current production rates range from $100 \text{ m}^3/\text{d}$ to $700 \text{ m}^3/\text{d}$ of emulsion targeting 3,500 kPa
- **Electric Submersible Pump (ESP)**
 - ESP for thermal SAGD applications can be sized to meet the specific deliverability of the well
 - Operating temperatures typically below 215°C
 - Typically install Series 500; Series 400 pumps installed due to casing restrictions
- **Progressive Cavity Pumps (PCP)**
 - Generally PCPs have been used for low deliverability wells and where potential solids may be produced.*
 - Installation of metal to metal pumps

* ConocoPhillips initial strategy for PCPs was to use them on low deliverability wells where the current ESP designs were deemed less appropriate. However, installation of larger PCP are being considered for wells that may produce relatively “cold” viscous fluid for some time.

ESP Run Life Definitions

- **MTTF:** This run-life measure is calculated as the total exposure time of all systems (running, pulled and failed) divided by the number of failed systems.
- **Average Runtime:** This run-life measure is calculated as the total exposure time of all systems (running, pulled and failed) divided by the number of systems (running, pulled and failed)
- **Average run life running ESP:** This run-life measure is calculated as the total exposure time of running systems divided by the number of running systems.
- **Window:** window time allows for changes in average run-life to be more apparent, as they are less obscured by previous data.

ESP Performance

KPI's

Population: 145 ESP's

Cumulative MTTF: 40.5 months

Windowed MTTF:** 61.1 months

Average Runtime: 16 months

Windowed* Runtime: 16.7 months

Average run life running ESP: 15.1 months

2016: 16 ESP failures

2017: 19 ESP failures


2018: 26 ESP Failures

2019: 2 ESP Failures


*(730 day window)

** The unrealistically high MTTF at S2 as a result of the # of recent ESP installs artificially increases the **One Surmont's** overall MTTF

MTTF



Average Runtime




Instrumentation in Wells

Subsection 3.1.1 (5)

Temperature & Pressure Measurement


- Temperature Measurement
 - Producer lateral temperature
 - Measured with 8 thermocouples, 40 LxData, or DTS fiber optic strings.
 - Injector lateral temperature
 - No temperatures measured
- Pressure Measurement
 - Producer
 - Primary bottom hole pressure measurement is done with a bubble tube corrected for TVD
 - Some LxData wells were equipped with toe pressure sensors, but have questions around accuracy
 - Secondary BHP measurement through 2 1/16 guide string
 - Injector
 - Primary bottom hole pressure measurement is done with casing blanket gas

SAGD Well Instrumentation



- 1. Phasing out all Thermocouples & LX Data at ESP conversion - evaluating options however DTS is the likely choice for most wells.**


Phase 2 SAGD Well Instrumentation



1. Phasing out all Thermocouples & LX Data at ESP conversion, evaluating options however DTS is the likely choice for most wells.
2. All wells will contain fiber temperature instrumentation.

Distributed Temperature Sensing (DTS)




No Change in 2018



Typical Observation Well Measurement

Soft cable Thermocouple (TC) strings were replaced by hard cable TC strings for improved well integrity

- Example thermocouple and piezometer (101-07-OBA)
- Typically 40 TC (2m spacing)
- 0-10 piezometers placed at varying intervals




4D Seismic

Subsection 3.1.1 (6)

4D Seismic Location Map – Phase 1

Phase 1 Area



Pilot

- Buried analog single component geophones
- Cased dynamite shots (1/4 Kg) @ 9 m
- 14th monitor acquired in September 2015

Pad 101N

- Buried analog single component geophones
- Cased dynamite shots (1/8 Kg) @ 6 m
- 9th monitor acquired in March 2018

Pad 101S

- Buried analog single component geophones
- Cased dynamite shots (1/8 Kg) @ 6 m
- 9th monitor acquired in March 2015

Pad 102N

- Buried analog single component geophones
- Cased dynamite shots (1/8 Kg) @ 6 m
- 10th monitor acquired in October 2018

Pad 102S


- Buried analog single component geophones
- Cased dynamite shots (1/8 Kg) @ 6 m
- 7th monitor acquired in October 2018

Pads 103 and 104

- Buried analog single component geophones
- Cased dynamite shots (1/8 Kg) @ 6 m
- 3rd monitor acquired in October 2017 (103)

4D Seismic Location – Phase 2












Phase 2 Area



Phase 2

- Buried analog single component geophones
- Cased dynamite shots (1/8 Kg) @ 6 m
- Acquired in three stages:
 - Initial 11 DA's: 2010-11
 - South extension: 2013-14
 - North extension: 2014-2015
- First Monitors
 - Spring 2016: 263-2
 - Fall 2016: 263-1 / 264-1 / 265-2 / 264-3
 - Spring 2017: 262-2/261-3/262-3/263-2 (*) /264-2
 - Fall 2017: 262-1
 - Spring 2018: 266-2
- Second Monitors:
 - Fall 2017: 263-1/264-1/265-2/264-3
 - Spring 2018: 262-2/261-3/262-3/263-2
 - Fall 2018: 262-1
- Third Monitor
 - Fall 2018: 263-1

Phase 1 - 4D Seismic Program

| PAD | 2015 | | 2016 | | 2017 | | 2018 | |
|-------|---|---|---|---|--------|---|---|---|
| | Spring | Fall | Spring | Fall | Spring | Fall | Spring | Fall |
| 101N |  | | | | | |  | |
| 101S |  | | | | | | | |
| 102N |  | | | | | | |  |
| 102S | | | |  | | | |  |
| Pilot | |  | | | | | | |
| 103 | | |  |  | |  | | |
| 104 | | | | | | | | |









Baseline



Monitor

Phase - 2 4D Seismic Program

| PAD | 2018 | |
|-------|---|---|
| | Spring | Fall |
| 263-1 | |  |
| 264-1 | | |
| 265-2 | | |
| 264-3 | | |
| 262-1 | |  |
| 266-2 | | |
| 262-3 |  | |
| 263-2 |  | |
| 264-2 | | |
| 262-2 |  | |
| 261-3 |  | |



Baseline




Monitor


2015 - 4D Seismic Results Pad 101

- Well Pair 07/08/09, without a true baseline.
- 4D anomaly volume have increased for the remaining well pairs.
- Good conformance, especially at the heel.

101 North 8th monitor - March 2015




101 North 9th monitor - March 2018




- 4D anomaly volumes have increased.
- Continued conformance improvement along Well Pad 10, 11, 16, 17.
- Infill wells drilled between Well Pads 10, 11, 12, 16, 17 and 18 to optimize production in a geological more complex zone.

101 South 8th monitor - March 2014



101 South 9th monitor - March 2015




● = 4D anomaly
~60 deg C Isotherm


2016 4D Seismic Results Pad 102 (102S)

- No a significant 4D Thermal growth between the Monitors

102 North 9th monitor - April 2015




102 North 10th monitor - October 2018





- No a significant 4D Thermal growth between the Monitors


102 South 6th monitor - October 2016



102 South 7th monitor - October 2018



2017 4D Seismic Results Pad 103



- Relative good conformance in most of well pair.
- 4D indications of coalescence with thermal chamber of Pad 101N (103-08/12)

2018 4D Seismic Results Phase 2

- **Spring Monitor:**

- 262-2
- 266-2
- 261-3
- 263-2
- 262-3


- **Fall Monitors:**

- 263-1
- 262-1


- **Relative good conformance in most well pairs**
(excepting 264-2 - deformation issues in the liner caused some wells to fail and impacted the quality of circulation on other wells, especially at the toe)



= 4D anomaly
~60 deg C Isotherm



S2 Monitors - 2018 (Spring - Fall)




4D Seismic Program 2018

- 4D seismic has proven very useful in monitoring and optimizing conformance and pressure strategy.
- 4D correlates with observation well data.
- Continuing to optimize heel/toe production/injection splits using 4D results.
- Ongoing efforts to history match reservoir models using 4D seismic.


Scheme Performance

Subsection 3.1.1 (7)

Surmont: Production vs. Scheme Approval



Surmont: Phase 1 and 2 - SOIP and RF




| DA | Area (m2) | Thickness NCB (m) | Phie in NCB % | So in NCB % | Cumulative Prod (e3m3) | SOIP (e3m3) | Current RF % |
|-------|-----------|-------------------|---------------|-------------|------------------------|-------------|--------------|
| 101N | 1,090,775 | 35.53 | 32.58 | 82.40 | 2,706 | 7,884 | 34.33 |
| 101S | 1,064,692 | 37.43 | 33.19 | 80.41 | 4,363 | 8,647 | 50.46 |
| 102N | 975,251 | 31.14 | 32.71 | 80.29 | 2,908 | 6,992 | 41.60 |
| 102S | 1,019,252 | 34.17 | 31.32 | 74.33 | 4,442 | 7,165 | 61.99 |
| 103 | 1,022,239 | 42.8 | 32.21 | 78.62 | 2,492 | 10,504 | 23.72 |
| 261-3 | 1,000,542 | 44.77 | 32.00 | 78.07 | 1,002 | 8,071 | 12.41 |
| 262-1 | 996,252 | 39.59 | 31.74 | 80.05 | 1,478 | 7,863 | 18.80 |
| 262-2 | 974,291 | 38.63 | 33.13 | 78.56 | 859 | 8,286 | 10.37 |
| 262-3 | 943,213 | 44.28 | 32.76 | 78.21 | 623 | 9,445 | 6.59 |
| 263-1 | 1,271,315 | 36.14 | 32.98 | 79.36 | 1,925 | 8,854 | 21.74 |
| 263-2 | 998,219 | 40.9 | 32.44 | 78.06 | 1,356 | 8,978 | 15.10 |
| 264-1 | 1,033,834 | 39.45 | 32.89 | 79.71 | 864 | 8,901 | 9.71 |
| 264-2 | 1,011,337 | 42.08 | 32.65 | 78.22 | 834 | 9,860 | 8.46 |
| 264-3 | 1,209,485 | 37.51 | 31.97 | 75.58 | 1,442 | 9,803 | 14.71 |
| 265-2 | 917,433 | 38.75 | 32.54 | 76.83 | 1,668 | 6,910 | 24.14 |
| 266-2 | 949,974 | 42.99 | 32.83 | 80.08 | 1,312 | 9,040 | 14.52 |

- **SOIP: 6,910 – 10,504 E3M3**
- **Current RF: 6.6% - 62.0%**
- **Porosity: 30.3% - 34.0%**
- **Oil saturation: 72.1% - 82.7%**
- **Blowdown timing will determine final EUR/RF.**
- **Recovery factors for drainage areas are based on performance. At this time, the expected ultimate recovery factor is difficult to predict, and these values are subject to change.**


| | Expected Recovery Factor | | |
|-------|--------------------------|-----------------------|-----------------------|
| | Tier 1: RF \geq 70% | Tier 2: RF \geq 50% | Tier 3: RF \geq 30% |
| 101N | | x | |
| 101S | | x | |
| 102N | | x | |
| 102S | x | | |
| 103 | x | | |
| 261-3 | | x | |
| 262-1 | | x | |
| 262-2 | | x | |
| 262-3 | | | x |
| 263-1 | x | | |
| 263-2 | | x | |
| 264-1 | | x | |
| 264-2 | | | x |
| 264-3 | | | x |
| 265-2 | | x | |
| 266-2 | | x | |

Surmont Phase 1 Aggregate Performance Plots


Rates (m3/d)



Well Status - Surmont 1




iSOR / cSOR (sm3/sm3)




- 101-P08, 101-P09 and 102-P01 were re-drilled due to poor performance; stranded resource at the toe was the primary reason (bridge plug was set previously to mitigate hotspot/sand production from these areas)
- NCG Trial ongoing for 102N, 102S and 101N
- Strong performance on Pad 103

Performance / Chamber Development Challenges – Pad 102N


Rates (m3/d)



Pressure (kPa)







102N



2018 (Fall)

- Performance and recovery on the west side of the pad has been challenged.
- NCG injection has commenced.


Performance / Chamber Development Challenges – Pad 102N




- 102-P01;02;03 have been the poorest producers on the pad due a combination of liner failures and poor geology.
- 102-P01 was re-drilled and artificial lift was changed to ESP.

Good Performance – WP 103-08

Rates (m3/d)




ISOR / cSOR (sm3/sm3)




TVDSS

103-08

2017 (Fall)




Temp (degC) vs Depth (mDKB)




- High quality reservoir.
- Falloff data and 4D seismic indicates well conformance.

Average Performance – 103-11

Rates (m3/d)




iSOR / cSOR (sm3/sm3)




TVDSS

103-11

2017 (Fall)




Temp (degC) vs Depth (mDKB)




- Poor conformance has seen this well perform average compared to others on this pad.
- Removed heel scab liner to help improve performance.

Obs Wells Temp & GR – 103-P10-OBB, 103-P12-OBA




103-P10-OBB 100/03-23-083-07W4 / 3.3m offset




103-P12-OBA 105/14-14-083-07W4 / 41.3m offset

Pad 103




Poor Performance – WP 102-03

Rates (m3/d)




ISOR / cSOR (sm3/sm3)




TVDSS

102-03

2018 (Fall)




Temp (degC) vs Depth (mDKB)



- Recovery remains low, and a side-track re-drill is being considered to recover the lateral wellbore length and increase production.

NCG Pilot / Pad 101N, 102N and 102S



Observations


- Reduction of emulsion rates
 - Reduction of water cut
 - iSOR reductions of 15-30%
 - Increase in chamber pressures due to NCG injection
 - Individual drainage areas under pilots are in full coalescence.
- } Oil rates flat

Phase 1 – Key Learnings


- Highly connected systems present complex redevelopment opportunities on 101S.
- 102N and 102S continues to see a reduction of emulsion, water cut and iSOR with the NCG pilot.
- 101N performance has improved late time due to both redevelopment executions as well as steam strategy adjustments.
- Liner installed flow control devices at pad 103 continue to outperform slotted liner wells.
- Optimization continues to improve performance of mature wells:
 - NCG pilot on-going for 101N, 102N and 102S.
 - Completed three re-drills in 2018.
 - Well stimulations (executed seven)
 - 100% of the well stimulations have been successful in terms of reducing the scale/dP across the production liner. This has contributed to higher production rates and a decreased risk of liner failure.

Surmont Phase 2 Aggregate Performance Plots


Rates (m3/d)



ISOR / cSOR (sm3/sm3)




Well Status - Surmont 2




- Top water thief zone interactions in Pads 263-1, 264-1, 264-3, and 265-2
- Bottom water thief zone interactions in 261-3, 262-1 and 262-2.
- Ten producers re-drilled; seven due to poor performance and three to failure.
- Two injectors re-drilled; one to poor performance and one due to failure.
- ESP conversions ongoing.

Performance / Chamber Development Challenges – Pad 262-3


Rates (m3/d)



Pressure (kPa)




262-3






2018 (Spring)

- 262-3 was operating at a target pressure of 4,000 kPag for most of 2018 but was reduced to 3,800 kPag in Q4.
- Challenged performance from East to West.
- No thief zone issues.

Performance / Chamber Development Challenges – Pad 262-3




262-3-P09-OB8 35.7 meters from well pair




V.E=5:1

- Limited chamber growth

Performance / Chamber Development Challenges – Pad 262-2



262-2




Bottom Water

2018 (Spring)


- Severe bottom water interaction on many well pairs.
- Reduced pressure differential between chamber and low pressure bottom water on wells that are interacting with the bottom water.

Good Performance – 263-1-07


Rates (m3/d)



ISOR / cSOR (sm³/sm³)




Temp (degC) vs Depth (mDKB)





263-1-07

2017 (Fall)




- Well Performance continues to exceed expectations.
- Mud channel continues to cause challenges with hotspots.

Surmont: Obs Wells Temp & GR – 263-1-P06-OBC, 263-1-P09-OBD



Average Performance – WP 264-1-01

Rates (m3/d)




iSOR / cSOR (sm3/sm3)




264-1-01

2017 (Fall)




V.E=5:1

Temp (degC) vs Depth (mDKB)




- Stable 2018 production performance, meets expectations.
- Managed top thief zone interaction with dedicated pressure management.


Surmont: Obs Wells Temp & GR – 264-1-P02-OBA, 264-1-P04-OBD



264-1-P02-OBA 102/11-22-083-06W4 / 33.5m offset




264-1-P04-OBD 102/14-22-083-06W4 17.0m offset




Poor Performance – WP 262-2-07

Rates (m3/d)




ISOR / cSOR (sm3/sm3)




262-2-07

2018 (Spring)




V.E=5:1

Temp (degC) vs Depth (mDKB)




- Challenged well; bottom water interaction.
- Minimum steam injection; pressure support from adjacent wells.

Surmont: Obs Wells Temp & GR – 262-2-P06-OBA, 262-2-P07-OBC




262-2-P07-OBC 100/09-34-083-06W4 / 9.1m offset




262-2-P06-OBA 100/10-34-083-06W4 40.3m offset

Pad 262-2



Observations





- Reduction of emulsion rates
 - Reduction of water cut
 - iSOR reductions of 15-30%
 - Increase in chamber pressures due to NCG injection
 - Individual drainage areas under pilots are in full coalescence.
- } Oil rates flat







Phase 2 - Key Learnings

- At pad 262-3, higher reservoir chamber pressure has been trialed to overcome under performance with minimal success. 262-3-P03 and 262-3-P12 were re-drilled and have observed a production increase, which is still under evaluation for sustainment.
- Injector steam splitters are still being evaluated for hotspot and thief zone mitigation.
- Bottom water has been very challenging to mitigate due to the early interaction of some wells and the high differential pressure between chamber and the bottom water zone.
- Top water interaction is being mitigated thanks to dedicated pressure management and ESP conversion strategy.
- Optimization continues to improve performance of mature wells:
 - NCG pilot on-going for 265-2.
 - Completed twelve re-drills in 2018.
 - Well stimulations (executed seven)
 - 100% of the well stimulations have been successful in terms of reducing the scale/dP across the production liner. This has contributed to higher production rates and a decreased risk of liner failure.



Surmont: Phase 1 Well Pad Rates and SOR / Pad 101



Surmont: Phase 1 Well Pad Rates and SOR / Pad 102




Surmont: Phase 1 Well Pad Rates and SOR / Pad 103




Surmont: Phase 2 Well Pad Rates and SOR


262-1 Rates (m3/d)




266-2 Rates (m3/d)




262-1 iSOR / cSOR (sm3/sm3)




266-2 iSOR / cSOR (sm3/sm3)




262-2 Rates (m3/d)




261-3 Rates (m3/d)



262-2 iSOR / cSOR (sm3/sm3)




261-3 iSOR / cSOR (sm3/sm3)



Surmont: Phase 2 Well Pad Rates and SOR


Rates (m3/d)

262-3




Rates (m3/d)

263-2



iSOR / cSOR (sm3/sm3)

262-3




iSOR / cSOR (sm3/sm3)

263-2




Rates (m3/d)

263-1




Rates (m3/d)

264-1




iSOR / cSOR (sm3/sm3)

263-1



iSOR / cSOR (sm3/sm3)


264-1



Surmont: Phase 2 Well Pad Rates and SOR


Rates (m3/d)

264-2




Rates (m3/d)

264-3




iSOR / cSOR (sm3/sm3)

264-2




iSOR / cSOR (sm3/sm3)

264-3



Rates (m3/d)

265-2



iSOR / cSOR (sm3/sm3)

265-2



Future Plans

Subsection 3.1.1 (8)

Future Plans – Surmont


- Continue evaluating NCG co-injection Pilots in Surmont for mid-life pressure management and thief zone mitigation.
- Evaluating multilateral well technology trial to drill infill producers off of existing SAGD producers.
- Well stimulations ongoing to determine the optimal chemical product for SAGD well scale treatment in Surmont.
- Evaluating infill opportunities.
- ESP conversions ongoing.
- Evaluation of steam optimization retrofits and their possible mitigation under thief zones interactions.
- Evaluate redevelopment opportunities for under performing pads.

Surface Operations and Compliance Surmont Project Approval 9426


Facilities

Subsection 3.1.2 (1)

Phase 1 Plot Plan: CPF




Phase 1 Plot Plan: Pad 101




- E-SAGD Equipment was de-commissioned in 2017; no major modifications in 2018

Phase 1 Plot Plan: Pad 102




- No Major Modifications in 2018

Phase 1 Plot Plan: Pad 103




- No Major Modifications in 2018

Phase 2 Plot Plan: CPF




Installation of one additional OTSG and associated heat exchanger at Surmont 2 in 2017, OTSG is now operational. No other major changes 2018.

Phase 2 Plot Plan: Pad 261-3




- No Major Modifications in 2018

Phase 2 Plot Plan: Pad 262-1




- **No Major Modifications in 2018**

Phase 2 Plot Plan: Pad 262-2



- No Major Modifications in 2018

Phase 2 Plot Plan: Pad 262-3



- No Major Modifications in 2018


- **No Major Modifications in 2018**



- **No Major Modifications in 2018**




Phase 2 Plot Plan: Pad 264-1




- No Major Modifications in 2018

Phase 2 Plot Plan: Pad 264-2



- No Major Modifications in 2018

Phase 2 Plot Plan: Pad 264-3




- No Major Modifications in 2018

- **No Major Modifications in 2018**




Phase 2 Plot Plan: Pad 266-2




- No Major Modifications in 2018

Plant Schematic: Phase 1



Plant Schematic: Phase 2



2018 Surmont Operations

- **Phase 1:**

- NCG co-injection pilot
- Pad 103 turn-around
- WLS turbine failure and replacement


- **Phase 2**

- Pad 264-1 turn-around
- Continuous operation with partial condensate blending
- Trial to turn off the glycol trim heater
- Wellhead freeze mitigation trial
- Repair planning and design for building sumps


Facility Performance

Subsection 3.1.2 (2)

Facility Performance: Bitumen Treatment by CPF




Facility Performance: Bitumen Treatment by Train




Facility Performance: Phase 1 Water Treatment

- Phase 1 water treatment plant continues to operate as per design.
- July 2018 outage required for WLS repairs was completed successfully.
- Monitoring of the sludge pond interstitial space is ongoing.




Facility Performance: Phase 2 Water Treatment

- Phase 2 water treatment plant operated as per design.
- Continued work to improve reliability of chemical feed systems.
- Produced water flowrates impacted by production curtailment in January 2019.



Facility Performance: Phase 2 Saline Water Treatment and Blowdown Evaporators

- Saline water treatment plant operating as per design. Saline water flowrates varied as per water balance make-up requirements.
- Predominantly operated with a single OTSG blowdown evaporator. Trials with dual blowdown evaporator operation began in late February 2019.



Surmont : Steam Generation Performance & Path Forward

- Twenty-three OTSGs were in operation throughout 2018 at Surmont:
 - 4 OTSGs in service at Surmont 1
 - 19 OTSGs in service at Surmont 2
- Surmont targeted 85% steam quality across the entire OTSG fleet until December 2018 when the quality targets were decreased
 - Corrosion of the pipes on the Surmont 2 OTSGs drove the decision to operate at steam qualities <85% in 2019
 - Root cause of the OTSG piping corrosion is under investigation
 - OTSG corrosion investigation and repairs led to individual OTSG outages throughout the last half of 2018.
 - The operating steam qualities remain above the design conditions of 75%
- Targeting 365+ days between OTSG outages for pigging (tube cleaning)


***2019 focus is to maintain online reliability while maximizing steam output**

Facility Performance: Electricity Consumption Surmont 1




- Phase 1 is at a steady state of production and electrical consumption, however the turn around in July caused the anomaly in 2018.

Facility Performance: Electricity Consumption Surmont 2




- Reduced power requirement in summer shows slight variation.


Facility Performance: 2018 Total Gas Usage




Surmont Facility Performance: 2018 Usage by Type



Facility Performance: 2018 Gas Usage by Location



Surmont Facility Performance: Year over Year Total Gas Usage



Surmont Facility Performance: 2018 Gas Usage - Highlights

High variability in Fuel Gas usage, due to production curtailments, driving lower steam demand and changes to target steam quality.

- Average 21 of 23 OTSGs running
- Steam quality increased from average 83% in 2017 to average 84.3% in 2018
- In December 2018, Steam Quality is decreased targeting an average 82%

After successful trial, NCG co-injection has been extended after November 2018 from 9 wells to 40 wells by end of February 2019. Gas co-injected with steam is assumed to remain in the reservoir (does NOT return with solution gas to plant).

Surmont Facility Performance: Flare/Vent Events

All efforts made to reduce and/or minimize Flare and Vent Events


Vent Events

- Met 2018 requirement for detecting, estimating and reporting gas volumes associated Vent Events
- Major events due to Power Outages, Product Shipment restrictions and VRU Trip
- Minor events due to increased product volatility after incorporating some condensate as diluent. This issue is being addressed through the “Alternate Blending Project” to be completed in 2019

Flare Events

- Major Events - July and August due to External Power Supply Failure, causing Plant Trips
- Minor events due to process upsets or extreme cold weather

Facility Performance: Greenhouse Gas




- As of 2018 Phase 1 and Phase 2 CO2e emission are reported as one combined value.
- 2018 GHG Emission intensity is currently being verified for payment submission.

Measurement and Reporting

Subsection 3.1.2 (3)

Well Testing

- Surmont Well Pads are configured to automatically and sequentially, align each production well into the Test Separator.
- Well Test Duration, Total Produced Emulsion, Average Water Cut and Total Produced Water Vapors are recorded for each Well Test.
- Well Test Results are reviewed to: “Approve”, if representative of the wells production, or “Reject.”
- Well Test Durations range from 5 to 10 hours, with up to 4 hours purge, based on the wells previous liquid production rates.



Well Estimated Monthly Production

Each well's estimated monthly production is calculated using only “*approved*” Well Test Results. Daily estimated volumes are used to calculate the wells monthly estimated volume from the time of an approved well test, until its next approved well test.

Well Monthly Estimated Oil Production =

Well Estimated Daily Oil Production × Hours per Days in Operation

- Well Estimated Daily Oil Production =

$$\frac{\text{Test Produced Emulsion Volume} \times (1 - \text{WC}\%)}{\text{Test Duration (hours)}} \times 24 \text{ hours}$$

Well Monthly Estimated Water Production =

Well Estimated Daily Water Production × Hours per Days in Operation

- Well Estimated Daily Water Production =

$$\frac{\text{Test Produced Emulsion Volume} \times \text{WC}\% + \text{Water Vapor}}{\text{Test Duration (hours)}} \times 24 \text{ hours}$$

Well Allocated Oil Production

Well Estimated Monthly Oil Production × Oil Proration Factor

- Oil Proration Factor =

$$\frac{\text{Battery Produced Oil}}{\text{Total Estimated Monthly Oil Production}}$$

- Battery Produced Oil =

$$\text{Oil Dispositions} + \text{Battery Tank Inventory} + \text{Shrinkage} - \text{Receipts} + \text{Well Load Oil}$$

- Total Estimated Monthly Oil Production =

$$\sum_{i=1}^x \text{Well}_i \text{ Estimated Monthly Oil Production}$$

where x is the total number of production wells for the reporting period.

- Oil Dispositions =

$$\text{Sales CTM}^1 + \text{Enbridge Tank Inventory} + \text{TruckOut}$$

- Oil in Battery's Tank Inventory =

$$\text{Sales Oil Tanks} + \text{OffSpec Tanks} + \text{Slop Oil Tanks} + \text{Skim Oil Tanks}$$

- Receipt =

$$\text{Diluent CTM}^1 + \text{Diluent Tank Inventory} + \text{Diluent TruckIn}$$

Well Allocated Water Production

Well Estimated Monthly Water Production × ***Water Proration Factor***

- Water Proration Factor =

$$\frac{\text{Battery Produced Water}}{\text{Total Estimated Monthly Water Production}}$$

- Battery Produced Water =

$$\text{Water Dispositions} + \text{Battery Tank Inventory} - \text{Receipts} + \text{Well Load Water}$$

- Total Estimated Monthly Water Production =

$$\sum_{n=1}^x \text{Well}_n \text{ Estimated Monthly Water Production}$$

where x is the total number of production wells for the reporting period.

- Water Dispositions =

$$\text{Dispositions to Injection Facility} + \text{Truck-Out}$$

- Water in Battery's Tank Inventory =

$$\text{Skim Oil Tanks} + \text{Slop Oil Tanks} + \text{DeSand/BackWash/ORF Tanks} + \text{Sales/OffSpec/Diluent Tanks}$$

- Receipt =

$$\text{IF Condensate Returns} + \text{Water in Diluent} + \text{Truck-In}$$

Well Allocated Oil Production × GOR

- Gas to Oil Ratio (GOR) =

$$\frac{\text{Battery Produced Gas}}{\text{Battery Produced Oil}}$$

- Battery Produced Gas =

$$\text{Gas Dispositions} - \text{Receipts}$$

- Gas Dispositions =

$$\text{Battery Utility FG} + \text{Steam Generators FG} + \text{NCG CoInjection} + \text{Flare/Vent} + \text{Camp}$$

- Receipt =

$$\text{TCPL Fuel Gas CTM}^1$$


As of January 2018, accounting and reporting of Vent Gas Events

¹ CTM: Custody Transfer Meter

Well Measured Steam × Steam Proration Factor

- Well Measured Steam =
Steam Injected @Heel + Steam Injected @Toe
- Steam Proration Factor =
$$\frac{\text{Steam Produced}}{\text{Total Measured Steam}}$$
- Steam Produced =
Steam Generated (CPF) – Steam Condensate Returns
- Total Measured Steam =
$$\sum_{n=1}^x \text{Well}_n \text{ Measured Steam}$$

where x is the total number of injection wells during the reporting period.



2018 Highlights and Changes

Completed Phase 1 Steam Volume Correction back to January 2015 to ensure adequate evaluation of field's performance

Non condensable gas (NCG) co-injection:


- **November 2016** Trial in 3 wells at Pad 102 (volumes estimated)
- **September 2017** Extended to 6 additional wells in Pad 102 (measured)
- **August 2018** Decision to include Pad 265-2, 12 wells (measured)
Metering of Pad 102 initial 3 wells NCG volumes
- **December 2018** Installation of NCG Meters in Pad 101 North (11 wells)

NCG Co-injected volumes added to battery's gas dispositions (assumes gas co-injected with steam does not return to the injection facility with solution gas)


Continue to maintain proration factor regulatory compliance through all 2018, through multiple production curtailments

- Total of 183 wells in SAGD operation

Oil and Water Production Proration Factors



Steam Injection Proration Factor



Water Production, Injection and Uses

Subsection 3.1.2 (4)

Surmont Phase 1 and Phase 2 Water Source Wells

Surmont Phase 1 Non-Saline Water Source Wells


| Source Well | Observation Well | Formation | Water Act Licence No. |
|------------------|------------------|--------------------|-----------------------|
| 1F1021808306W400 | 1F2021808306W400 | Lower Grand Rapids | 00253532-02-00 |
| 1F1041808306W400 | 102041808306W400 | Lower Grand Rapids | 00253532-02-00 |
| 1F1011908306W400 | 100011908306W400 | Lower Grand Rapids | 00253532-02-00 |
| 1F1032308307W400 | 100032308307W400 | Lower Grand Rapids | 00253532-02-00 |

Surmont Phase 2 Non-Saline Water Source Wells

| Source Well | Observation Well | Formation | Water Act Licence No. |
|------------------|------------------|--------------------|-----------------------|
| 1F1022108306W400 | 100022108306W400 | Lower Grand Rapids | 00312463-01-00 |
| 1F1022608306W400 | 100022608306W400 | Lower Grand Rapids | 00312463-01-00 |
| 1F1052808306W400 | 100052808306W400 | Lower Grand Rapids | 00312463-01-00 |
| 1F1070308306W400 | 1F2070308306W400 | Lower Grand Rapids | 00312463-01-00 |
| 1F1101408306W400 | 1F1111408306W400 | Lower Grand Rapids | 00312463-01-00 |
| 1F1130508306W400 | 100130508306W400 | Lower Grand Rapids | 00312463-01-00 |
| 1F1153408307W400 | 1F2153408307W400 | Lower Grand Rapids | 00312463-01-00 |


Surmont Phase 2 Saline Water Source Wells

| Source Well | Formation |
|------------------|--------------------|
| 1F1020308404W400 | Clearwater |
| 1F1020608404W400 | Clearwater |
| 1F1033008304W400 | Lower Grand Rapids |
| 1F1042208305W400 | Clearwater |
| 1F1071308305W400 | Clearwater |
| 1F1081008305W400 | Lower Grand Rapids |
| 1F1101708404W400 | Clearwater |
| 1F1160908404W400 | Clearwater |
| 1F2091708404W400 | Lower Grand Rapids |
| 1F2141108404W400 | Lower Grand Rapids |




No Changes in 2018

Surmont Non-Saline and Saline Water Source Wells Production Volumes




Water Production and Steam Injection Volumes




Directive 081: Injection Facility Water Imbalance

- Surmont in compliance with *Directive 081* Injection Facility Water Imbalance since June 2014
- Surmont Phase 2 CPF Shutdown planned for Q2-2019




Directive 081: Annual Disposal performance



- Surmont anticipates *Directive 081* disposal limit compliance in 2019 as per current trend (7.0% actual vs. 10.7% disposal limit)
- Surmont accomplished *Directive 081* compliance in 2016 (7.5% actual vs. 10.6% disposal limit) after commissioning brackish water system and blowdown evaporators at Phase 2 CPF


Surmont Phase 1 Water Disposal Wells

| Well | Zone Approved for Disposal | Maximum Wellhead Injection Pressure (kPa) | Well Status | AER Disposal Approval No. |
|----------------------|----------------------------|---|----------------|---------------------------|
| 100/01-16-083-05W4/0 | McMurray | 2700 | Water Disposal | 10044K |
| 100/07-22-083-05W4/0 | McMurray | 2500 | Water Disposal | 10044K |
| 100/08-10-083-05W4/0 | McMurray | 2300 | Water Disposal | 10044K |
| 100/04-21-083-05W4/0 | McMurray | 2500 | Water Disposal | 10044K |
| 100/01-11-083-05W4/0 | McMurray | 2500 | Water Disposal | 10044K |




Surmont Phase 2 Water Disposal Wells


| Well | Zone Approved for Disposal | Maximum Wellhead Injection Pressure (kPa) | Well Status | AER Disposal Approval No. |
|----------------------|----------------------------|---|----------------|---------------------------|
| 100/01-09-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 100/01-04-083-05W4/0 | McMurray | 2500 | Water Disposal | 10044K |
| 102/08-21-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 100/01-28-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 100/10-15-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 102/15-15-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 100/08-27-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 100/08-23-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |
| 100/16-24-083-05W4/0 | McMurray | 3400 | Water Disposal | 10044K |




Surmont Water Disposal Wells Injection Rates (McMurray)




Surmont Phase 1 Water Disposal Wells Well Head Pressure (McMurray)




Surmont Phase 2 Water Disposal Wells Well Head Pressure (McMurray)



Water Disposal Well 100/01-16-083-05 W4M Observation Well Pressure (McMurray)



Water Disposal Well 100/08-10-083-05 W4M Observation Well Pressure (McMurray)



Waste Disposal

| Waste Description | Disposal Weight (Tonnes) | Disposal Method |
|--------------------------------|--------------------------|------------------------------------|
| Dangerous Oilfield Waste | 12,969 | |
| Hydrocarbon/Emulsion Sludge | 436 | Oilfield Waste Processing Facility |
| Crude Oil/Condensate Emulsions | 8,462 | Oilfield Waste Processing Facility |
| Various | 4,071 | Landfill |
| Non-Dangerous Oilfield Waste | 36,498 | |
| Lime Sludge | 27,632 | Landfill |
| Various | 8,688 | Landfill |
| Well Fluids | 178 | Cavern |

Waste Recycling

| Waste Description | Disposal Weight (Tonnes) | Disposal Method |
|-------------------------|--------------------------|--------------------|
| Oil | 6 | Used Oil Recycler |
| Empty Containers | 4.6 | Recycling Facility |
| Fluorescent Light Tubes | 1.1 | Recycling Facility |
| Batteries | 2.8 | Recycling Facility |


Typical Water Analysis

| Parameter | Non-Saline Makeup Water (mg/L) | Saline Makeup Water (mg/L) | Produced Water (mg/L) | Disposal Water (mg/L) |
|---------------------------------|--------------------------------|----------------------------|-----------------------|-----------------------|
| pH | 8.5 | 8.2 | 7.5 | 11.8 |
| Total Dissolved Solids (TDS) | 1,400 | 8,000 | 1,800 | 23,000 |
| Chloride | 200 | 2,800 | 650 | 9,500 |
| Hardness as CaCO ₃ | <0.5 | 225 | 10 | 5 |
| Alkalinity as CaCO ₃ | 900 | 350 | 250 | 2,700 |
| Silica | 8 | 7 | 190 | 225 |
| Total Boron | 6 | 3.3 | 40 | 260 |
| Total Organic Carbon | 15 | 4 | 500 | 2,150 |
| Oil Content | <1 | <1 | 65 | 30 |

Sulphur Production


Subsection 3.1.2 (5)

Daily SO₂ Emissions




- The SO₂ emissions were managed below the 1.6t/d in 2018.
- The facility instituted operational controls to reduce Sulphur scavenger chemical in October 2018.

2018 Surmont Project Sulphur Recovery




- Sulphur recovery unit maintained 100% uptime.
- Surmont achieved greater than the required 69.7% quarterly Sulphur recovery in 2018.

Ambient Air Quality Monitoring




Continuous ambient air monitoring: all Alberta Ambient Air Quality Objectives were met in 2018

Ambient Air Quality Monitoring



Continuous ambient air monitoring: all Alberta Ambient Air Quality Objectives were met in 2018

Ambient Air Quality Monitoring



Continuous ambient air monitoring: all Alberta Ambient Air Quality Objectives were met in 2018

Environmental Compliance

Subsection 3.1.2 (6)

Environmental Compliance and Monitoring

- ConocoPhillips maintained complete environmental compliance throughout 2018 with no environmental non-conformances at Surmont Phase 1 or 2.

Environmental Monitoring

Groundwater Monitoring Program:

- Program revised to focus monitoring on early change detection

Wetlands:

- Semi-annual wetland site assessments completed

Wildlife Monitoring Program:

- Wildlife handling permit obtained
- Submitted a Comprehensive Wildlife report in May of 2018
- Continued support of the Monitoring Avian Productivity and Survivorship program
- No serious nuisance wildlife or human-bear interactions

Reclamation Work:

- Submitted Project Level Conservation, Reclamation and Closure Plan in October 2018
- Completed monitoring of vegetation establishment on reclaimed trial sites
- Established bioengineering trials for erosion and sediment control

Environmental Initiatives

- Canada's Oil Sands Innovation Alliance (COSIA) - ConocoPhillips is an active participant of the Water, Land and Greenhouse Gas Environmental Priority Area and the COSIA Monitoring Priority Area
- ConocoPhillips leads the industrial Footprint Reduction Options Group (iFROG), a collaboration of in situ oil sands operators, to address key knowledge gaps related to wetland reclamation

Compliance Confirmation and Non Compliances

Subsection 3.1.2 (7) + (8)

Compliance Confirmation and Non Compliances

ConocoPhillips is in regulatory compliance for 2018 with the exception of the following:

Surmont Warm Line Softener and Boiler Feed Water Tank Farm Secondary Containment

- Visual inspection of the berm area identified small punctures on two areas that were exposed for inspection on Oct 29, 2019.
- Compromised areas were repaired with patches followed by sand layers and geotextile.
- Probe sampling continues on other areas to test for additional signs of instability.

Surmont Unplanned Hydrocarbon Venting

- Unplanned hydrocarbon venting events exceeding 4hrs in duration were reported on May 7th, 2018 and June 17, 2018.
- ConocoPhillips' Voluntary Self Disclosure (July 24, 2018) was accepted by the AER with conditions to provide quarterly updates on the venting until the new VRU is installed in mid/late 2019.
- A new educator vapour recovery unit (VRU) is planned for installation during the plant turnaround in summer 2019. The system is expected to be operating by Q3 2019.

Surmont Building Sumps - Primary Liners

- 17 building sumps contain liquid in the interstitial spaces.
- AER accepted ConocoPhillips' Voluntary Self Disclosure on Sept 26, 2018 with a condition to provide quarterly updates (ongoing).
- A number of sumps were repaired online with no interruption to operations, the remainder of the sump repairs require a full plant outage, scheduled for May of 2019.
- CPC is on track to complete all the required repairs to return the sumps to compliance by the end of Q4 2019.

Compliance Confirmation and Non Compliances

Boiler Feed Water Release 5-18-83-6W – Sept 21, 2018- FIS Incident: 20182998

- PSV lifted early and was discharging 9 m3 of boiler feed water as the OSTG was being warmed up.
- The PSV lifted 2000 kpa earlier than what it was set to lift at.
- The valve was taken out of the recertification program and discarded.
- The environmental impact was limited to soil and water contamination. Fluid was cleaned up from the culvert to the source. Incident investigation was closed, no remedial actions are required.

Steam Condensate Release-2-5-84-6W4 – Nov 14, 2018- FIS Incident: 20183493

- 2 inch steam line had developed a pinhole leak releasing 12 m3 steam and steam condensate.
- the transmitter which controls the electric heating coil on the two inch line was positioned too close to the 4 inch line. This resulted in most of the 2 inch line not receiving sufficient heat. As a result part of the line froze.
- Environmental clean up is complete and the investigation is closed, no remedial actions are required.

Future Plans

Subsection 3.1.2 (9)

Future Plans – Surmont

- Surmont Landfill project design is complete, potential execution in 2020

Phase 1:

- Design work on-going for modifications for 100% condensate blending with potential construction in 2020
- NCG co-injection pilot ongoing and potential expansion in 2019

Phase 2:

- Full plant turn-around planned for April – June 2019
- Ongoing construction for modification for 100% condensate blending with start up planned for October 2019
- New Eductor VRU system construction and start up during 2019 turn-around
- Continuing repair planning and design for building sumps and starting execution

Future Pad Developments

