



# **PENGROWTH ENERGY CORPORATION**

## **LINDBERGH SAGD PROJECT**

### **2019 ANNUAL PERFORMANCE PRESENTATION**

#### **SCHEME APPROVAL 6410T**

2020 01 15


# SUBSURFACE ISSUES: TABLE OF CONTENTS

1. Brief Background of the Scheme
2. Geology/Geoscience
3. Drilling and Completions
4. Artificial Lift
5. Instrumentation in Wells
6. Seismic
7. Scheme Performance
8. Future Plans

# BACKGROUND AND OVERVIEW





# PROJECT LOCATION



# PROJECT OVERVIEW AND HISTORY

- Murphy piloted and then commercialized CSS production in the Lloydminster and Rex formations in Section 13 from 1972-1998
- Pengrowth acquired the Lindbergh lease from Murphy Canada in April, 2004
- All CSS wells have been abandoned
- Pilot project implemented to evaluate the SAGD recovery process in the Mannville Lloydminster Formation
  - 2 pilot SAGD wells – began steam circulation Feb 2012
- 12,500 bpd SAGD facility completed Q4, 2014
  - 20 new SAGD wells – began steam circulation Dec 2014
  - 1 new SAGD well/2 Infill wells – began steam circulation June 2017
  - 6 new SAGD wells – began steam circulation Sept 2017
  - 3 new SAGD wells – began steam circulation Feb 2018
  - 8 infill wells – began steam circulation July 2018
- Pilot SAGD CPF decommissioned upon start-up of the Phase 1 CPF and then recommissioned in April 2018 to handle increasing production from the field.
- Approved to increase production to 40,000 bpd



## CSS IMPACT ON FUTURE DEVELOPMENT IN SEC 13


- Murphy produced a total of 2.3 MMbbls of oil and 7.6 MMbbls of water with 8.2 MMbbls (CWE) steam injection
- 71 vertical wells and 3 horizontal wells used in CSS operations
- The average recovery factor for the CSS area is 5-6% of the OOIP (up to 10% in various wells)
- CSS injection operations were at pressures over 10 MPa with injection at various depths within the target formation
- Pengrowth received D78 Category 2 Amendment Approval to install 2 additional horizontal well pairs on well pad 4 to test SAGD production performance in the CSS impacted area. 1 well pair was drilled in 2017 and placed on circulation in September.
- Potential impacts of the CSS operations are:
  - Channeling of steam, breakthrough to bottom water, increased SOR with decreased recovery, increased water production from residual CSS steam condensate
- Performance of D04-06 drilled in the CSS area in 2017 has been as expected
- The success of drilling and producing D04-06 has de-risked future production from this part of the reservoir

# LINDBERGH APPLICATION HISTORY

OPERATOR	DATE	EVENT
Murphy	May 1991	ERCB Scheme Approval 6410 granted
	Aug 1993	ERCB Amended Scheme Approval 6410B granted
	Dec 1996	ERCB Amended Scheme Approval 6410C granted
	Aug 1997	ERCB Amended Scheme Approval 6410D granted
	Jun 1999	ERCB Amended Scheme Approval 6410E granted
Pengrowth	Apr 2004	ERCB Amended Scheme Approval 6410F granted
	July 2011	Scheme Amended - 6410H SAGD Pilot project granted
	Aug 2012	Scheme Amended - 6410I Expansion to 12,500 bopd granted
	Apr 2014	Scheme Amended - 6410J Solvent soak trial granted
	Nov 2014	Scheme Amended – 6410K Facility de-bottlenecking
	Jun 2015	Scheme Amended – 6410L Section 13 addition
	May 2016	Scheme Amended – 6410M EIA approval to 30kbbbl/d
	Nov 2016	Scheme Amended – 6410N Infill wells
	May 2017	Scheme Amended – 6410O Legacy well remediation scheduling
	Jun 2017	Scheme Amended – 6410P Phase II treater addition to 40kbbbl/d
	May 2018	Scheme Amended – 6410Q Gas co-injection
	Dec 2018	Scheme Amended – 6410R Expansion of project dev area
	May 2019	Scheme Amended – 6410S Cogeneration addition
Sep 2019	Scheme Amended – 6410T Additional well pairs and infills	

# SAGD RECOVERY PROCESS

- Stacked horizontal wells
- Steam injected into top well and forms steam chamber
- Steam condenses on boundary of chamber and releases heat into the bitumen
- Bitumen and condensed water drain by gravity to the bottom well
- Bottom well produces liquid bitumen to surface







# GEOLOGY AND GEOSCIENCE



# 2019 DRILLING

- No wells drilled at Lindbergh
- No wells drilled at Muriel Lake
- 5 well pairs and 13 infill wells planned for 2020




## BITUMEN VOLUMES & RESERVOIR PROPERTIES


- All values shown for  $S_w$ ,  $\Phi$  and bitumen volume are measured from the Petrel geological model which was recently updated
- Boundaries defining the area and the top and bottom surfaces of the reservoir are used to confine the volume calculation
- Bitumen volume extends below well pairs to the 10 ohm.m resistivity level
- $S_w$ ,  $\Phi$  are averages for the volume shown
- Average horizontal permeability = 3500 md:  $K_v / K_h = 0.86$
- Viscosity of the bitumen decreases upwards through the reservoir from approximately 600,000 cP at the base to 50,000 cP near the top
- Mean reservoir thickness over entire lease is 16.7 m. This includes all areas having a minimum thickness of 10 meters
- Initial reservoir temperature = 20 Celsius, initial reservoir pressure 2800-3000 kPa
- Reservoir pressure in bottom water interval = 2850 kPa
- Reservoir depth ~ 500 mKB

Region	OBIP Volume (E3m <sup>3</sup> )	Porosity (%)	Sw (%)
<b>Wellpad D01</b>	1,407.5	36	19
<b>Wellpad D02</b>	2,160.1	35	21
<b>Wellpad D03</b>	2,886.5	35	17
<b>Wellpad D04</b>	4,295.3	36	22
<b>Wellpad D05</b>	3,493.0	37	20


# REPRESENTATIVE COMPOSITE WELL LOG





Average Pay Thickness = 20m  
 Average Producer to Injector Spacing = 5 m  
 Average O/W to Producer Distance = 3 m




# NET BITUMEN PAY




# STRUCTURAL TOP AND BOTTOM OF BITUMEN RESERVOIR



# CAPROCK THICKNESS MAP




# CORED WELLS AND SPECIAL CORE ANALYSIS



Core analysis typically consists of the following:

- Dean-Stark – 1762 samples
- Small plug  $\Phi$ , K, Sw, - 2100 samples
- Grain size – 39 wells sampled
- Petrographic, XRD – 50 samples from 15 wells
- Special core analysis – 140 samples from 20 wells





# TYPICAL LINDBERGH CORE SAMPLE

- Lloydminster sands are continuous and contain rare shale interbeds
- Typically the reservoir is composed of very fine grained sands throughout the interval

1AA/16-24-058-05W4

480.1 m




454.1 m


Top of Lloydminster

# PETROGRAPHIC ANALYSIS


- Some Petrographic analysis has been done on core samples in the Lloydminster Reservoir
- Sands are typically classified as Feldspathic Litharenite to Sublitharenite on the Folk scale (Folk, 1974)
- The clay fraction is less than 10% of the bulk sample
- Grain sizes range from coarse silt to lower medium grained sand
- Critical velocity testing indicates that clays remain non-mobile during steam injection. The clays will not block pore throats



# REPRESENTATIVE CROSS SECTION THROUGH PROJECT AREA



# REPRESENTATIVE MODEL CROSS SECTION THROUGH PROJECT AREA




- Producer planned to land 3 m above highest point on oil/water contact (OWC) surface
- LWD measurements indicated OWC rising to the north
- Needed to directionally control drilling to maintain offset from OWC

# HEAVE MONUMENTS

- Baseline readings were taken in March 2012
- Most recent observations were taken in February and September of 2014
- Based on current analysis we do not anticipate additional monitoring within the next year

		Point Differences vs Observation 1		
		$\Delta N(m)$	$\Delta E(m)$	$\Delta Elev(m)$
Observation 6 (February 2014)	Control	0	0	0
		0	0	0
	WP01	0.051	-0.05	0.019
		-	-	0.002
	WP02	0.022	-0.003	0.003
		0.014	0.011	0.019
	0.046	-0.107	0.003	
Observation 7 (September 2014)	Control	-	-	0.0022
		0	0	0
	WP01	-	-	0.0019
		-	-	0.0029
	WP02	0.016	0.008	0.004
		0.012	0.021	0.011
	0.044	-0.09	0.005	
	0	0.001	0.003	



# CAPROCK INTEGRITY AND RESERVOIR OPERATING PRESSURE

- Mini-frac testing was done on the 1AB/13-13-58-5W4 (March 2011), 100/13-24-58-5W4 (December 2011), and 1AF/10-13-58-5W4 (March 2014)
  - All showed – comparable results
- Approved maximum ongoing operating pressure = 5500 kPa, less than 80% of minimum stress in caprock at reservoir depth


Pengrowth 1AB/13-13-58-05W4M						
Zone	TVD m	Min Stress		Vert Stress		Stress Regime
		MPa	kPa/m	MPa	kPa/m	
Lloydminster	512.0	5.94	11.60	10.74	20.98	V. frac
GP Zone #1	493.0	7.48	15.17	10.34	20.97	V. frac
GP Zone #2	484.0	7.55	15.60	10.15	20.97	V. frac
GP Zone #3	476.0	6.80	14.29	9.97	20.95	V. <u>Frac</u>

- Caprock Shale Core Preservation on 1AF/10-13-58-5W4 in March 2014 shows several fractures

PENGROWTH 1AF/10-13-058-05W4				
Fracture No.	Formation	Fracture Type	Depth (m)	Dip (Degrees)
F1	GP	Small fracture	480.6	65
F2	GP	Small Fracture	480.9	70
F3	GP	Small Fracture	482.9	70
F4	GP	Hairline fracture	484.2	60

# LINDBERGH SEISMIC

- 102 sq km of 3D data exist over most of the Lindbergh and Muriel Lake leases with exploitable resource
- 1.32 sq km 4D Seismic over D01 wellpad:
  - Baseline acquired Feb 2012
  - First monitor acquired Dec 2013
  - Second monitor acquired Dec 2016
- No new seismic acquired in 2019



# — DRILLING AND COMPLETIONS






## COMMERCIAL DRILLING & COMPLETIONS

- No new SAGD well pairs or infill well additions in 2019

# TYPICAL SAGD PAIR CIRCULATION COMPLETION




## LINER DESIGN

- The relatively small grain size, the presence of fines in the reservoir and combined laboratory flow testing indicated a liner slot width of 0.009” would be required
- This small slot width can lead to quality control problems in the manufacturing process
- The presence of fines with the small slot widths increased the potential for slot plugging
- Therefore, Pengrowth chose to utilize wire wrap screens with a 0.009” wrap for the producer well liners
  - This increased the open flow area from about 2.5% to over 9%
- Straight cut slots were utilized in the injector wells


## LINER DESIGN

- Pilot wells utilize 219.1 mm slotted liners in the injector wells and 219.1 mm wire wrap screens in the producer wells
- Phase 1 Commercial wells utilize 177.8 mm slotted liners in the injector wells and 177.8 mm wire wrap screens in the producer wells
- Both Pilot and Phase 1 Commercial well pairs are completed with the same slot and wire wrap screen design
- Wellbore was downsized from the Pilot to the Phase 1 Commercial wells to optimize drilling costs and complexity as the larger liners were not required for forecast flow rates
- Inflow control devices
  - Liner deployed systems have been installed in five producer wells (D05-P08, D03-P01, D04-P06, D04-P07, D04-P08) across the field to test the performance in variable pay thicknesses, with bottom water interaction and overall steam chamber conformance
  - Application of the first ICD system installed in well D05-P08 (started-up in 2015) has been deemed a success as this has been one of the highest performing well pairs across the field
  - Metrics that PGF is using to measure success is produced emulsion rates, overall well pair operation (steam injection rates and ESP stability), subcool control and inflow characteristics based on downhole temperature data

# TYPICAL SAGD PAIR ARTIFICIAL LIFT COMPLETION



# D05 INFILL WELL TYPICAL COMPLETION



# COMPLETION CHANGES

- Scab liners
  - Initially installed in the producers based on shut-in temperature profiles across the lateral, drill profiles of the injector and producer and steam splitter locations in the injectors
  - Typical target landing depth is approximately 75-80% of the lateral length to aid in toe development early in SAGD production and mitigate flow breakthrough at the heel
- Mechanical perforation or recompletion of scab liner
  - Mechanical perforation performed concurrently with pump changes where applicable in past years
  - Pengrowth has transitioned to scab liner recompletes (pulls, redesigns) over mechanical perforation based on learning's over several years
  - Both options open flow to selected intervals along the scab liner
    - Wells and corresponding perforation intervals selected based on fall off temperature response; typically targeting areas of high subcool that would indicate cooler stranded emulsion
    - All Lindbergh well pairs are continually being monitored and analyzed for possible scab liner modifications to optimize production and reservoir conformance
  - Scab liner recomplete is preferred over mechanical perforation
    - Avoid scale deposition in the liner upon cutting the tubing
    - Workover risk and cost is comparable with both methods
    - Scab liner remains structurally intact by recompleting and not perforating base pipe

## COMPLETION CHANGES

- Well D05-P07 had a tubing-conveyed ICD (first in the field) installed in June 2018
  - Pulled original scab liner (installed in 2015), cleaned out lateral and installed tubing-conveyed ICD string to mitigate high vapour production and improve overall reservoir conformance
  - Production results following the workover have been favorable and led to further use of ICD systems across the Field
- Two tubing-conveyed ICD systems installed in December 2018 to remediate failed liners resulting in favorable production results from both wells
- Two commercial scab liners pulled and re-landed in 2019 to optimize well conformance, producer drawdown and production rates
- One commercial scab liner installed in 2019 to remediate a failed liner, mitigate vapour production and optimize well conformance
- Metrics that PGF is using to measure success of tubing-conveyed ICD systems is very similar to liner-conveyed ICD's; produced emulsion rates, overall well pair operation (steam injection rates and ESP stability), subcool control and inflow characteristics based on downhole temperature data



# SAGD INJECTOR COMPLETION CHANGES

Well Name	Well Type	UWI	Steam Splitter(s) Installed	Shifted Open	Shifted Closed
D02-J04	Injector	106082505805W40	1		
D02-J06	Injector	108082505805W40	1		
D02-J07	Injector	109082505805W42	1		
D03-J03	Injector	103122405805W40	1		
D03-J04	Injector	104122405805W40	1	Nov-15	Nov-17
D03-J05	Injector	105122405805W40	2		
D03-J06	Injector	106122405805W40	1	Nov-15	Sep-16
D03-J07	Injector	102092305805W40	1		
D04-J01	Injector	105152405805W40	1		
D04-J02	Injector	106152405805W40	1		
D04-J03	Injector	107152405805W40	1	Jan-18	
D04-J04	Injector	109152405805W40	1	Jan-18	Jul-19
D04-J05	Injector	104162405805W40	1	Dec-17	Jul-19
D04-J06	Injector	109101305805W40	1		
D04-J07	Injector	108162405805W42	1		
D04-J08	Injector	109162405805W40	1	May-18	
D04-J09	Injector	110162405805W40	1	May-18	
D05-J03	Injector	109012305805W40	1	Nov-15	
D05-J04	Injector	110012305805W40	1		
D05-J06	Injector	107042405805W40	1	Nov-15	

# SAGD PRODUCER COMPLETIONS CHANGES

Well Name	Well Type	UWI	Scab Liner Installed	Production Ports Installed	Scab Liner Perforated	Scab Liner Pulled/Relanded
D01-P01	Producer	106062405805W42	Y	0		
D01-P02	Producer	108062405805W40	Y	1		
D01-P03	Producer	114062405805W40	N	Liner-conveyed ICD		
D02-P04	Producer	102082505805W40	Y	1		
D02-P05	Producer	100082505805W40	Y	1	17-Jul	
D02-P06	Producer	103082505805W40	Y	1	16-Oct	
D02-P07	Producer	104082505805W40	Y	1		
D02-P08	Producer	105082505805W42	Y	1	16-Jun	
D03-P01	Producer	103112405805W40	Y	1	17-Sep	
D03-P02	Producer	102112405805W40	Y	0		May-19
D03-P03	Producer	107122405805W40	Y	1		
D03-P04	Producer	102122405805W40	Y	1		
D03-P05	Producer	108122405805W40	Y	1		Dec-18
D03-P06	Producer	109122405805W40	Y	1		
D03-P07	Producer	103092305805W40	Y	1	16-Jul	
*D04-P01	Producer	102152405805W40	N	Tubing-conveyed ICD		Dec-18
D04-P02	Producer	103152405805W40	Y	2		
D04-P03	Producer	104152405805W40	Y	2		
D04-P04	Producer	108152405805W40	Y	2		
D04-P05	Producer	103162405805W42	Y	2		
D04-P06	Producer	108101305805W40	N	Liner-conveyed ICD		
D04-P07	Producer	105162405805W40	N	Liner & tubing – conveyed ICD		Dec-18
D04-P08	Producer	106162405805W40	Y	Liner-conveyed ICD		Nov-19
D04-P09	Producer	107162405805W43	Y	2		
D05-P01	Producer	104012305805W42	Y	1	17-Jul	
D05-P02	Producer	105012305805W40	Y	1	17-Jan	
D05-P03	Producer	106012305805W40	Y	2		
D05-P04	Producer	103012305805W40	Y	1		
D05-P05	Producer	102042405805W40	Y	1	17-Sep	
D05-P06	Producer	103042405805W40	Y	1	16-Dec	
*D05-P07	Producer	104042405805W40	N	Tubing-conveyed ICD	18-Jun	
D05-P08	Producer	105042405805W40	N	Liner-conveyed ICD		

\*Original scab liner pulled and tubing-conveyed ICD system installed

# INFILL WELL COMPLETIONS CHANGES

Well Name	Well Type	UWI	Scab Liner/Tail pipe Installed	Production Ports Installed	Scab Liner/Tail Pipe Perforated	Scab Liner/Tail Pipe Pulled/Relanded
D01-INF01	Infill	102052405805W40	N	0		
D01-INF02	Infill	113062405805W42	Y	0		
D05-INF01	Infill	111012305805W40	Y	0		Oct-19
D05-INF02	Infill	112012305805W40	Y	0		Oct-19
D05-INF03	Infill	113012305805W40	Y	0		
D05-INF04	Infill	114012305805W40	Y	0		Oct-19
D05-INF05	Infill	110042405805W40	Y	0		May-19
D05-INF06	Infill	111042405805W40	Y	0		
D05-INF07	Infill	112042405805W40	Y	0		
D05-INF08	Infill	113042405805W40	Y	0		Oct-19

# COMMERCIAL ARTIFICIAL LIFT

- Required to convert from circulation to typical SAGD operations
- All SAGD producers and Pilot infill wells utilize high temperature ESP's
  - Vendor and pump type selected based on expected well performance, target landing locations and historical run life
  - Pumps rated to 260°C
- D05 infill wells utilize hydraulic lift rod pump systems
  - Lower capital cost when compared to ESP, better for higher viscosity emulsion, more variability in re-steaming operations if required
- Pumps designed to handle full flow rate range from initial install through ramp up to peak emulsion rates
- Vapour interference in the pump has been higher than anticipated in certain cases
  - Mitigating operational problems due to higher vapour loading through the use of AGH stages in ESP's and completion modifications
- Continuing to work closely with ESP vendors to improve performance and run time
- Run time improvement due to decreased start/stops as a result of improved plant reliability
- Technological improvements and advancements
  - Higher temperature motors
  - Improved seal systems
  - Improved bearing design
  - Shorter design resulting in less stress running in severe doglegs

## DRILLING SCHEDULE

New drilling subject to market conditions, internal approval and regulatory approval where applicable.

- Future considerations pending internal approval
  - 5 well pairs and 13 infill wells planned for 2020



# INSTRUMENTATION



## SAGD WELL PAIR INSTRUMENTATION

- Single point pressure measurement is taken at the heel of both the injector and producer via bubble tube
  - Methane is injected in the casing of the injector and in the guide string annulus of the producer to provide a reading at surface via a pressure transmitter
  - Gas gradient calculations are accounted for in the pressure reading
  - Purging of the bubble tubes is completed on an as needed basis to limit the overall volume of gas being injected
  - Differential pressure is monitored between the injector and producer to provide insight into the accuracy of the pressure reading and subsequent purge timing
  - Producer bubble tubes are purged more frequently than injector bubble tubes due to the guide string annular volume and potential for plugging
- Fiber optic DTS (distributed temperature sensors) are run in all of the producer and infills wells to provide real-time temperature data along the entire wellbore

# OBSERVATION LOCATIONS/ TYPICAL COMPLETION





## OBSERVATION LOCATIONS/ TYPICAL COMPLETION

- Downhole pressure/temperature gauge reliability has been good overall
  - As the thermocouple and pressure monitoring equipment is cemented on the backside of the casing, remediation of any failed downhole equipment is challenging
  - Pengrowth therefore runs multiple temperature and pressure points if this is encountered
- Surface equipment reliability has been an issue at times as all observation well locations rely on solar panels/battery combos for power
- Line of sight is also required for the Commercial observation wells to transmit data
- Pengrowth is continuing to work with the vendors on increasing the number of solar panels and battery capacity on location; especially important in winter months
- Data transmission accuracy is also being rectified between Pengrowth and the instrumentation vendors on an as needed basis
- Operations team checks locations monthly

# SCHEME PERFORMANCE




## PREDICTING SAGD PERFORMANCE


- SAGD well production type curves are created using historical production data on the pilot and phase 1 wells.
- Butler's equation is used to modify each type curve based on the geological data available.
- Infill wells are forecasted based on the production forecast of the parent well

# LINDBERGH PERFORMANCE

Lindbergh Monthly Overview



# CUMULATIVE VOLUMES



# PAD RECOVERIES

## OBIP - Recovery and % recovery by pad

	Thickness	Length <sup>†</sup>	Spacing	Ave $\phi$	Area	Ave So	OBIP	Recovery <sup>††</sup>	Recovery
Pad	(m)	(m)	(m)	(%)	(Ha)	(%)	(e3m3)	(e3m3)	(%)
D01 <sup>†††</sup>	19.5	828	100	36	24.8	81	1407.5	812.8	<b>57.7</b>
D02	19.0	817	100	35	40.9	79	2160.1	675.6	<b>31.3</b>
D03	18.1	787	100	35	55.1	83	2886.5	1087.8	<b>37.7</b>
D04	20.6	833	100	36	75.0	78	4295.3	452.1	<b>10.5</b>
D05	18.3	801	100	37	64.1	80	3493.0	1411.6	<b>40.4</b>

## Developed BIP - Recovery and % recovery by pad

	Thickness	Length <sup>†</sup>	Spacing	Ave $\phi$	Ave So	DBIP	Recovery <sup>††</sup>	Recovery	EUR
Pad	(m)	(m)	(m)	(%)	(%)	(e3m3)	(e3m3)	(%)	(%)
D01 <sup>†††</sup>	15.2	828	100	36	81	1093.6	812.8	<b>74.3</b>	80
D02	17.7	817	100	35	79	2012.8	675.6	<b>33.6</b>	70
D03	15.9	787	100	35	83	2526.2	1087.8	<b>43.1</b>	70
D04	16.3	833	100	36	78	3385.7	452.1	<b>13.4</b>	70
D05	16.3	801	100	37	80	3122.9	1411.6	<b>45.2</b>	70


<sup>†</sup> Length is average slotted length plus 25 meters per end (50 m total)

<sup>††</sup> Cumulative production to Oct 31 2019

<sup>†††</sup> D01 numbers include a new well pair and two new infill wells, D05 number include 8 new infill wells


# LINDBERGH DEVELOPED RECOVERY

Lindbergh Recovery by Pad



# PHASE 1 HIGH PERFORMER


D05-01 Overview






# PHASE 1 MEDIUM PERFORMER

D03-07 Overview




# PHASE 1 POOR PERFORMER

D02-05 Overview




# CUMULATIVE WATER/STEAM RATIO



# NCG INJECTION IN PAD D05


- NCG injection was commenced at Pad D05 in August 2019
- Gas injection was ramped up to 1 mol% over a 3 month period
- Steam volume was cut by 10 to 15% per WP without a negative impact in oil production
- Steam to oil ratio has been reduced from 3.5 to 3.0
- Gas mol fraction will be slowly increased within the limits of AER approval
- Planning to initiate gas injection in Pad D01




# D01-02 OBSERVATION WELL EXAMPLE



102\_06-24-58-05W4M0 - Temperature



# LINDBERGH CSOR AND ISOR



## WELLHEAD STEAM QUALITY

- Current steam quality injected at the well pad is ~98%
  - Close proximity to CPF

## PAD ABANDONMENTS – 5 YEAR OUTLOOK

- No abandonments of SAGD wells or well pads are expected in the next 5 years



## KEY LEARNINGS

- D05 infill wells meeting expectations
  - Learnings on circulation strategy will be incorporated into future infill well plans
- D05 NCG Injection meeting expectations
  - Current target of 1 mol% of gas injection has resulted in ~12% steam savings with no negative impact on oil production
- Successful drilling and circulation of 2 SAGD well pairs in previously depleted cyclic steam stimulation area.
  - Significant de-risking of reserves
- Reduced steam chamber operating pressure
  - Managing steam chamber pressure slightly above bottom water pressure to optimize SOR
- Well bore hydraulics optimization
  - Production ports in the scab liner and shift-able ports in the steam injection string improve well conformance
  - Scab liner perforating (select cases) has proven beneficial during pump changes to improve wellbore conformance, pump operation and well KPI's
  - Liner and tubing deployed flow control devices showing encouraging results
- Continuous improvement in ESP run life

# FUTURE PLANS - SUBSURFACE



## FUTURE PLANS - SUBSURFACE

- Future considerations pending internal approval
  - Drilling of 4 SAGD well pairs in Pad D02 and 1 well pair in PadD03
  - Drilling 13 new infill wells in Pads D02 and D03
  - Commence non-condensable gas co-injection with steam in Pads D01 and D03 and continue it in Pad 05


# FACILITIES



# LINDBERGH SAGD COMMERCIAL FACILITY


- SW-25-058-05 W4M CPF site
- Original daily design capacity
  - 8000 m<sup>3</sup>/d (50,000 bwpd) CWE for steam generation
  - 2208 m<sup>3</sup>/d (13,888 bopd) bitumen production
  - SOR 3.61
- Debottlenecked daily design capacity
  - 8000 m<sup>3</sup>/d (50,000 bwpd) CWE for steam generation
  - 3180 m<sup>3</sup>/d (20,000 bopd) bitumen production
  - SOR 2.5
- Commercial facility equipped with water recycle
  - Falling film mechanical Vapour compression
  - >90% water recycle rate
- Commercial facility first steam December 2014

# LINDBERGH COMMERCIAL CPF PLOT PLAN



		<b>SCOVAN ENGL. INC.</b> 2017.03.13 ISSUED FOR CONSTRUCTION		<table border="1"> <thead> <tr> <th>REV.</th> <th>DESCRIPTION</th> <th>DATE</th> <th>BY</th> <th>CHK.</th> <th>PC</th> </tr> </thead> <tbody> <tr> <td>3</td> <td>ADD/ACTO POLY TANK, E-105A, S/C EXCHANGERS, AND E-206/201 EXCHANGERS</td> <td>2017.08.16</td> <td>2017.03.13</td> <td>EPS</td> <td>OKR</td> </tr> <tr> <td>2</td> <td>ADD/ACTO CHIM. TANKS &amp; UPDATED ATTO TRANSFORMER LOCATION AND CONNECTION</td> <td>2013.206</td> <td>2015.06.16</td> <td>BOF</td> <td>OKR</td> </tr> <tr> <td>1</td> <td>ADD/ACTO LIFT &amp; DEBOTTLENECK EQUIPMENT &amp; UPDATED ITH CONNECTIONS</td> <td>2013.206</td> <td>2015.04.23</td> <td>BOF</td> <td>BSL</td> </tr> <tr> <td>0</td> <td>ISSUED FOR CONSTRUCTION</td> <td>2013.206</td> <td>2014.08.29</td> <td>BOF</td> <td>OKR</td> </tr> </tbody> </table>		REV.	DESCRIPTION	DATE	BY	CHK.	PC	3	ADD/ACTO POLY TANK, E-105A, S/C EXCHANGERS, AND E-206/201 EXCHANGERS	2017.08.16	2017.03.13	EPS	OKR	2	ADD/ACTO CHIM. TANKS & UPDATED ATTO TRANSFORMER LOCATION AND CONNECTION	2013.206	2015.06.16	BOF	OKR	1	ADD/ACTO LIFT & DEBOTTLENECK EQUIPMENT & UPDATED ITH CONNECTIONS	2013.206	2015.04.23	BOF	BSL	0	ISSUED FOR CONSTRUCTION	2013.206	2014.08.29	BOF	OKR			<b>LINDBERGH SAGO FACILITY</b> LSD: SW 25-58-05 W4M CENTRAL PROCESSING FACILITY PLOT PLAN	
REV.	DESCRIPTION	DATE	BY	CHK.	PC																																		
3	ADD/ACTO POLY TANK, E-105A, S/C EXCHANGERS, AND E-206/201 EXCHANGERS	2017.08.16	2017.03.13	EPS	OKR																																		
2	ADD/ACTO CHIM. TANKS & UPDATED ATTO TRANSFORMER LOCATION AND CONNECTION	2013.206	2015.06.16	BOF	OKR																																		
1	ADD/ACTO LIFT & DEBOTTLENECK EQUIPMENT & UPDATED ITH CONNECTIONS	2013.206	2015.04.23	BOF	BSL																																		
0	ISSUED FOR CONSTRUCTION	2013.206	2014.08.29	BOF	OKR																																		
DRAWING NO. 121110-M-PP-00-001-02 PLOT PLAN LEGEND		METEOROLOGICAL DRAWINGS		STAMPS APPLY TO CURRENT REVISION ONLY		SHEET NO. 03 OF 03 DRAWING NO. 121110-M-PP-00-001-01 DATE: 2017.03.13		TOTAL SHEETS: 3																															

# LINDBERGH PILOT PLOT PLAN



TAG	BUILDING/EQUIPMENT DESCRIPTION	WIDTH	LENGTH	HEIGHT
WATER TREATMENT BUILDING	19000	12000	5000	
PROCESS BUILDING	19000	4300	6100	
UTILITY BUILDING	8000	1900	3500	
FUEL GAS BUILDING	3700	7400	3000	
MAINTENANCE & ADMIN BUILDING	18000	14500	4100	
WINDSCREEN BUILDING	7300	13100	7100	
SOURCE WATER PUMP SKID	4000	5900	3600	
TEST LABORATORY BUILDING	7300	19000	6410	
STEAM GENERATOR BUILDING	22700	3940	6500	
PG RECEIVER SHED	1600	2800	—	
FLOOR AD BUILDING	1600	3200	2700	
MCC BUILDING	4000	10000	3600	
METER SHED	3000	7000	2100	
T-380 RAW WATER TANK	10000	—	6800	
T-385 BOILER FEED WATER TANK	10000	—	6800	
T-370 SOFTENER WATER TANK	9110	—	3600	
T-411 PRODUCTION GALLER TANK #1	7100	—	7800	
T-412 PRODUCTION GALLER TANK #2	7100	—	7800	
T-420 OFFSPEC OIL TANK	7100	—	7800	
T-390 SLURRY TANK	5600	—	7300	
T-340 DRAINAGE TANK	5000	—	7300	
T-400 FRESH WATER DRUM TANK	7100	—	9700	
T-410 DESAND TANK	4350	—	7300	
T-391 DESAND/WEIR TANK	4350	—	7300	
T-700 POP TANK	4350	—	7300	
T-700 FLOOR DRAIN TANK	4350	—	3600	
T-800 GLYCOL STORAGE TANK	2300	—	1800	
METERING PACKAGE FOR T-410	120	200	230	
V-302 VACUUM GENERATOR	1600	LD	1100	
V-303 STEAM BLOWDOWN SEPARATOR	1600	LD	1100	
E-219A/B COOLING GLYCOL AERIAL OCCUPERS	4000	13000	—	
FL-700 FLAME SENCE	2100	—	1800	
E-219S COOLING GLYCOL AERIAL OCCUPERS	4000	13000	—	
T-403 WATER TRANSFER TANK	8000	—	9700	
20-207 WATER TRANSFER PG LAUNCHER	1600	—	1200	
05-008 WATER TRANSFER PUMP SKID	4000	6700	4500	

GENERAL NOTES:  
 1. SEE COORDINATES C 00+000 & N 00+000 (AC RETROFITTED)  
 TO 17M COORDINATES E 00+000 & N 00+000

REV.	DESCRIPTION	JOB No.	DATE	BY	CHK	PH	PC
0	ISSUED FOR CONSTRUCTION	2010.008	2011.08.26	MM	GRD		
1	REVISED AS SHOWN	2010.008	2011.11.14	RF	BN		
2	UPDATED SOURCE WATER POND & ADDED DUNE WALL	2010.008	2012.06.20	RF	BN		
3	AS-BUILT	2010.008	2012.06.20	DBS	BN		
4	AERIAL DOCKER HOIST (E-905)	2012.008	2012.08.21	PH	RF		
5	ADDED WATER TRANSFER PUMP SKID, TANK AND PG LAUNCHER AREA	2012.008	2014.04.22	RCF	WDR		
6	REVISED WATER TRANSFER PUMP SKID, TANK AND PG LAUNCHER AREA	2012.008	2014.07.09	MM	GRD		

**PENGROWTH**


**SCOVAN Engineering**

LINDBERGH SAGD PILOT FACILITY  
 LSP: 07-15-058-05 W/M  
 CENTRAL PROCESSING FACILITY  
 PLOT PLAN

DATE:	2011.08.26
DRAWN BY:	A. FORNABBO
CHECKED BY:	A. FORNABBO
PROJECT ENGINEER:	A. BARNELL
PROJECT ENGINEER:	S. NELSON

SITE:	CPF
SCALE:	1:600
DRAWING NO.:	12-10-10-PP-001
REV.:	6


# LINDBERGH COMMERCIAL TYPICAL WELLPAD PLOT PLAN



D02 – 5 pairs    D03 – 7 pairs    D05 – 8 pairs    D04 – 6 pairs



# LINDBERGH SCHEMATIC



# LINDBERGH SAGD COMMERCIAL FACILITY MODIFICATIONS

- Debottlenecking Progress
  - Installed additional secondary glycol aerial cooler to improve produced water cooling at front end of facility.
  - Purchased additional produced water exchanger for future install.
  - Installed dry salt storage and conveyor system to reduce risk from challenging salt supply environment
- WELL PAD EXPANSIONS
  - No expansions completed in 2019.

## PILOT OPERATION

- No major regulatory equipment outages in 2019.
- Executed zero diluent bitumen treating trial.
- Produced Water from pilot transferred via pipeline to CPF for water treatment.
- Steam generation from the Pilot plant primarily feeds D01 Pad and is tied into the overall field distribution system.

# LINDBERGH SAGD COMMERCIAL FACILITY PERFORMANCE

- Bitumen treatment
  - Producing on spec oil with use of lighter density diluent from pipeline
- Water treatment
  - Increased hardness in the produced water causing more frequent regenerations of the softeners
  - Continual chemical treatment balancing in the evaporators to chelate any excess hardness
- H-710 Steam Generator regulatory outage October 2019


# LINDBERGH SAGD COMMERCIAL FACILITY PERFORMANCE

- Steam generation
  - Operating at full capacity
- Power
  - Generation steady outside of regular maintenance
  - Import/Export vary due to weather
    - Plant is islanded during thunderstorms
    - High line power is affected by thunderstorms, ice, human factors
  - Consumption increasing as loading on facility ramps up

# LINDBERGH – POWER CONSUMPTION


	Generation	Consumption	Import	Export
	MWh	MWh	MWh	MWh
Nov-17	11111	10346	517	1282
Dec-17	11483	10791	268	960
Jan-18	11285	10734	233	784
Feb-18	10625	10703	270	192
Mar-18	11676	11993	385	68
Apr-18	10667	10681	505	491
May-18	10005	9386	666	1285
Jun-18	9899	8858	37	1078
Jul-18	10120	9113	35	1042
Aug-18	10204	9905	145	444
Sept-18	10454	9244	2	1212
Oct-18	11012	11147	739	604
Nov-18	11716	12561	979	134
Dec-18	11462	12361	1179	279
Jan-19	13532	15154	1837	215
Feb-19	12005	12512	846	339
Mar-19	12526	13295	1332	563
Apr-19	11403	11517	589	475
May-19	12056	12267	360	149
Jun-19	11402	11959	640	83
Jul-19	11592	11790	512	314
Aug-19	11743	13282	1619	80
Sept-19	11838	13662	1828	4
Oct-19	12202	13760	2070	512

## LINDBERGH – FLARED & VENTED GAS



- There was no sour gas venting during this period

# LINDBERGH – SO<sub>2</sub> EMISSIONS



- Highest daily recorded SO<sub>2</sub> emissions were 1.82 t/day. SO<sub>2</sub> emission license limit is 3.0 t/day
- Considerations will be given to the incorporation of sulphur recovery for future Phase 2 expansion



# LINDBERGH – NO<sub>x</sub> EMISSIONS

CEMS Data - Monthly Average - H-720	
	NOx (kg/h)
Jan-18	13.19
Feb-18	15.27
Mar-18	14.92
Apr-18	14.69
May-18	14.31
Jun-18	13.99
Jul-18	13.40
Aug-18	14.23
Sep-18	14.22
Oct-18	14.18
Nov-18	15.39
Dec-18	14.15
Jan-19	15.44
Feb-19	15.47
Mar-19	13.50
Apr-19	13.87
May-19	13.74
Jun-19	14.05
Jul-19	13.06
Aug-19	13.12
Sep-19	14.80
Oct-19	15.27

2018 Manual Stack Surveys			2019 Manual Stack Surveys		
Emission Source	Date	NOx Emission Rate (kg/hr)	Date	NOx Emission Rate (kg/hr)	NOx Approval Limit (kg/hr)
H-710 (Steam Gen 1)	---	---	5-Nov-2019	15.4	16.6
H-720 (Steam Gen 2)	27-Mar-18	15.1	---	---	16.6
H-730 (Cogen 1)	1-Aug-2018	1.34	---	---	5.0
H-740 (Cogen 2)	---	---	4-Jul-2019	0.643	5.0

EPEA Approval 1581-02-03 Table 3.2 requires manual stack survey test frequency as:

- H-710 & H-720 once per year on a rotating basis
- H-730 & H-740 once per year on a rotating basis
- H-710 & H-720 one with CEMS (Continuous Emission Monitoring System)


# MEASUREMENT AND REPORTING



# MARP SUMMARY

- Testing
  - Test separator located at D01, D02, D03, D04, and D05
  - 12-24 hour tests
    - Within +/- 10% of previous results to be accepted
  - Individual well gas allocated as a function of facility GOR and monthly allocated production
  - Pad D03 utilizing AGAR meter and manual testing
  - Pad D01, D02, D04, and D05 utilizing manual testing
    - 2 samples captured per test to improve accuracy
  - Pad D01, D02, D04 and D05 to be converted to AGAR meter in 2020
    - Calibration of the test separator AGAR meters on-going; numerous calibration points throughout 2018 and 2019 but with the addition of new wells in 2018 manual samples were deemed more accurate until steady state
    - Capital constraints in 2019 also deferred AGAR calibration project

# PRORATION FACTOR




	2018-10	2018-11	2018-12	2019-01	2019-02	2019-03	2019-04	2019-05	2019-06	2019-07	2019-08	2019-09	2019-10
<b>Oil</b>	1.02	1.03	0.92	0.98	1.04	0.99	1.02	1.07	1.06	1.04	1.02	1.07	0.98
<b>Water</b>	0.97	0.99	0.96	0.98	0.98	0.99	0.96	1.01	0.99	0.96	1.00	0.98	0.92
<b>Steam</b>	1.02	1.02	1.02	1.01	1.01	1.02	1.02	1.01	0.99	0.99	0.99	0.99	1.00


# PRORATION IMPROVEMENT INITIATIVES

- Main issues associated with BS&W consistency
- Completed
  - Testing procedure (Sept 2015)
  - Chemical adjustments (Sept 2015)
  - Various piping changes for more accurate testing (2015-2016)
  - Pad D02, D03, D05 AGAR Calibrations (2016-2018)
  - Testing procedure review (2018/2019); 2 manual cuts per test and audit of test procedure and accuracy
- Ongoing (2020)
  - Pad D01 AGAR (new) calibration
  - Pad D04 AGAR (new) calibration
  - Pad D05 AGAR re-calibration testing
  - Pad D03 AGAR re-calibration testing
  - Pad D02 AGAR re-calibration testing

# COMMERCIAL MARP SCHEMATIC



# PILOT MARP SCHEMATIC



# MARP CALCULATION SUMMARY

## 7.1.2. Total Battery Bitumen Production

$$\text{Produced Bitumen} = ((O_s + DBI_c - DBI_o)/SF) - (D_i + D_{oi} - D_{ci})$$

	$((O_s$	$+$	$DBI_c$	$-$	$DBI_o)$	$/$	$SF)$	$-$	$(D_i$	$+$	$D_{oi}$	$-$	$D_{ci})$
Sales			Closing Inventory		Opening Inventory								
Oil			T-400, T-401, T-402, T-403, T-404, T-411, T-412, T-420 and T-430		T-400, T-401, T-402, T-403, T-404, T-411, T-412, T-420 and T-430		Blending Shrinkage Factor		Diluent Receipts		Opening Inventory T-405 and T-440		Closing Inventory T-405 and T-440

## 7.1.7. Battery Water Production

Dispositions	+	$\Delta$ Water Tanks	+	$\Delta$ De-oiling Tanks	+	$\Delta$ Slop Tank Water	+	$\Delta$ Off Spec Tank Water	-
Formula 7.1.8		Change in water tank inventory for T-300, T-301, T-325, T-450, T-460, T-400, T-401		Change in water inventory in T-311, T-313 & T-315		Change in water inventory in T-403, T-404 and T-430		Change in water inventory in T-402 and T-420	
Water received with diluent	-	FT-79303	-	Trucked in Water	-	FT-33306			
		Blowdown water from IF T-792		Water trucked into T-333 from outside sources		Utility water from IF to T-333			

## 7.1.8. Battery Water Dispositions

FT-33607	+	FT-2161	+	FT-2160	+	FT-33003	+	Sales Water	+	Other water out	+
Water Delivery to Injection Facility for Disposal		Produced Water Delivery to Injection for Disposal from Satellite		Blowdown Water Delivery to Injection for Disposal from Satellite		Water Delivery to IF for treatment		S&W content of sales dilbit blend		Water Content of other fluid trucked out	
FT-0158	-	FT-0289									
Wastewater to IF T-334		Produced water to CPF from Satellite									

## 7.3.1. Primary Steam Calculation

FT-71028	+	FT-72028	+	FT-73028	+	FT-74028	+	FT-5700
Steam to Pads from Steam Generator		Steam to Pads from Steam Generator		Steam to Pads from HRSG		Steam to Pads From HRSG		Steam to Pads from Satellite V-570

## 7.3.2. Secondary Steam Injection Calculation

FT-71401	+	FT-72401	+	FT-73302	+	FT-74302	+	FT-5102	+
BFW to Steam Gen H710 from T-700 BFW tank		BFW to Steam Gen H720 from T-700 BFW tank		BFW To Cogen H730 from T-700		BFW to Cogen H740 from T700		BFW to B-510	
FT5202	-	(FT-71306	+	FT-72306	+	FT-73211	+	FT-74211	+
BFW to B-520		Steam Condensate from Steam Gens		Steam Condensate from Steam Gens		Steam Condensate from HRSG		Steam Condensate from HRSG	
FT-2160)									
Pilot Steam Blowdown									



# WATER



## LINDBERGH WATER SOURCES

- 10-23-056-05 W4M river water station
  - Fresh water source from the North Saskatchewan River
  - AENV License No.13844
    - » Gross diversion, consumptive use: 2,272 acre-feet (2,802,467m<sup>3</sup>) annually
    - » Rate of diversion: 1.8 cubic feet per second (4403m<sup>3</sup>/d or 1,607,400m<sup>3</sup> annually)
- Commercial
  - ~888 m<sup>3</sup>/d make-up water usage at commercial and pilot facility (2019 to date average)
  - 2019 make up water usage increased because of the increased production at both the pilot and commercial facility

## LINDBERGH SOURCE WATER MAKE UP VOLUMES

- Commercial volumes used primarily for soft de-oiled water make-up and miscellaneous utility services

	Source Water (m3 per month)
Oct-18	26,442
Nov-18	23,048
Dec-18	24,188
Jan-19	29,386
Feb-19	25,146
Mar-19	29,779
Apr-19	19,765
May-19	26,146
Jun-19	24,992
Jul-19	27,334
Aug-19	30,284
Sept-19	28,399
Oct-19	28,468

2018 Total: 289,220 m3

2019 YTD: 269,700 m3

Source water requirements increased because of the increased production at both the pilot and commercial facility

# LINDBERGH COMMERCIAL DISPOSAL LIMITS

- The Lindbergh CPF is equipped with evaporator towers for PW recycle

	Produced Water (m3/month)	Disposal Water (m3/month)	Source Water Makeup (m3/month)	Disposal Limit (%)	Actual Disposal (%)
Oct-18	2,346,560	168,027	274,956	9.28%	6.47%
Nov-18	2,590,610	182,108	304,541	9.27%	6.40%
Dec-18	2,819,400	201,459	335,981	9.26%	6.39%
Jan-19	253,418	15,331	42,849	9.09%	8.30%
Feb-19	484,437	35,188	78,981	9.02%	6.25%
Mar-19	740,030	63,046	121,757	9.03%	7.34%
Apr-19	975,197	86,076	155,471	9.04%	7.63%
May-19	1,227,590	106,306	195,816	9.04%	7.74%
Jun-19	1,480,020	128,258	235,267	9.04%	7.48%
Jul-19	1,728,390	150,825	274,654	9.04%	7.53%
Aug-19	1,989,130	174,771	318,759	9.04%	7.65%
Sep-19	2,247,210	196,921	363,280	9.03%	7.58%
Oct-19	2,490,910	221,990	404,081	9.03%	7.73%

# LINDBERGH WATER QUALITY

## Raw Water Properties

Turbidity	5 – 1000 NTU
Suspended Solids	5 – 600 mg/l
Total Dissolved Solids	250mg/l
Total Hardness	170 ppm (as CaCO <sub>3</sub> )
Na	10.7
K	1.2
Mg	13.1
Ca	46.7
Chlorides	10.8 mg/l
Bicarbonate	180 mg/l
CO <sub>3</sub>	<0.50 mg/l
Sulphate	44.2
Total Alkalinity	150

## Produced Water Properties

Component	mg/l as ion	mg/l as CaCO <sub>3</sub>
Calcium (Ca <sup>++</sup> )	52.6	131.5
Magnesium (Mg <sup>++</sup> )	4.0	16.4
Sodium (Na <sup>+</sup> )	1660.0	3618.8
Potassium (K <sup>+</sup> )	61.2	78.3
Iron (Fe <sup>++</sup> )	0.1	0.2
Manganese (Mn <sup>++</sup> )	0.1	0.2
Hydrogen (H <sup>+</sup> )	0.0	0.0
Barium (Ba <sup>++</sup> )	0.7	0.5
Strontium (Sr <sup>++</sup> )	2.2	2.5
Sum Cations		3848.4
Bicarbonate (HCO <sub>3</sub> <sup>-</sup> )	257.0	210.7
Carbonate (CO <sub>3</sub> <sup>-</sup> )	0.0	0.0
Hydroxide (OH <sup>-</sup> )	0.0	0.0
Sulphate (SO <sub>4</sub> <sup>-</sup> )	10.0	10.4
Chloride (Cl <sup>-</sup> )	2880.0	4060.8
Sum Anions		4281.9
Total Dissolved Solids (measured)	5130.0	
pH (units)	6.8	
Temperature (°C)	21.4	
Total Hardness		150.0
Silica (SiO <sub>2</sub> )	264.0	
Conductivity (µS/cm)	8230	

## SAC Waste Properties

CATIONS			ANIONS			Total Dissolved Solids (mg/L)	
Ion	mg/L	meq/L	Ion	mg/L	meq/L	Measured	Calculated
Na	17300	752	Cl	32340	911	53000	53000
K	230	5.88	HCO <sub>3</sub>	130	2.12	1.039	1.339
Ca	2340	117	SO <sub>4</sub>	81.0	1.69	80200	0.12
Mg	195	16.0	CO <sub>3</sub>	<0.50	<0.02	6600	Resistivity (ohm-m) @25°
Ba	27.5	0.401	OH	<0.50	<0.03	13.9	110
Sr	101	2.30				6.62	FALSE
Fe	0.46	0.0164				Observed pH	R25 Spot Test
H+							

# LINDBERGH INDUSTRIAL RUNOFF MONITORING

Location	LSD	Number of Releases	Total Volume (m3)	pH	Oil and Grease	Chloride (mg/L)
CPF	04-25-058-05W4	5	58000	6.82 - 7.85	No sheen	6.9 - 35.3
Pilot	07-13-058-05W4	1	500	7.85	No sheen	24
Well Pad	15-24-058-05W4	9	3795	6.21 – 7.19	No sheen	<31
Well Pad	05-13-058-05W4	13	3410	6.80 – 7.89	No sheen	<31
Well Pad	11-13-058-05W4	13	1570	6.35 – 7.14	No sheen	<31
Well Pad	02-24-058-05W4	10	3250	6.68 – 7.34	No sheen	<31

- There were 51 surface water releases from Oct 2018 to Oct 2019
- Total volume discharged was 70,525 m<sup>3</sup>
- All laboratory analytical and field screening results were within license requirements for pH, oil and grease, and chloride

# DISPOSAL WELLS




## DISPOSAL WELLS

- 111/15-13-58-5W4
  - Well license number – 0126796
  - Disposal approval number – 5565
    - Completed in Basal Cambrian Sands
    - No rate limit
    - Max WHP – 10.9 MPa
  - Blowdown and/or produced water disposal (if required)
- 104/05-13-58-5W4 (DW4)
  - Well license number – 0454598
  - Disposal approval number – 12088
    - Completed in Basal Cambrian Sands
    - No rate limit
    - Max WHP – 13 MPa
  - Produced water disposal (if required)
- 100/08-26-58-5W4 (DW5)
  - Well license number – 0469115
  - Disposal approval number – 12088B
    - Completed in Basal Cambrian Sands
    - Screened completion
    - No rate limit
    - Max WHP – 12.6 MPa
  - Softener backwash and/or produced water disposal (if required)




## DISPOSAL WELLS


- Three water disposal wells (Basal Cambrian Sand) at ~ 1600 meters depth
- 11/15-13 disposes of Pilot blowdown or produced water
- 04/05-13 disposes of excess of produced water
  - Pilot was recommissioned in April 2018
- 00/08-26 was completed in November 2014 and disposes of softener regen or produced water
- All 3 wells are tied into the commercial CPF
  - 2 disposal streams into these wells are softener regeneration backwash and excess produced water




# DISPOSAL HISTORY - 104/5-13-58-5W4



# DISPOSAL HISTORY - 100/8-26-58-5W4



# DISPOSAL HISTORY - 111/15-13-58-5W4



## OFFSITE DISPOSAL VOLUMES AND LOCATIONS – OCT 2019

	NewAlta Elk Point (m3)	Tervita Lindbergh (m3)	Secure Edmonton (m3)	Secure Tulliby Lake (m3)	<b>Total Offsite (m3)</b>	05-13 Disposal (m3)	15-13 Disposal (m3)	08-26 Disposal (m3)
Oct-18	470	9027	374	0	<b>9,871</b>	1563	6700	1581
Nov-18	1227	6040	433	0	<b>7,700</b>	1094	6210	1699
Dec-18	2213	8487	210	0	<b>10,910</b>	1611	259	4537
Jan-19	146	11383	100	0	<b>11,629</b>	930	0	3374
Feb-19	2942	9109	0	0	<b>12,050</b>	2318	0	5220
Mar-19	8123	15308	0	0	<b>23,431</b>	1134	0	4386
Apr-19	1691	12493	0	0	<b>14,184</b>	5350	0	3811
May-19	537	11241	0	0	<b>11,778</b>	3546	0	4054
Jun-19	3860	9804	0	763	<b>14,427</b>	3581	571	3037
Jul-19	560	7099	0	5734	<b>13,393</b>	1451	6883	1279
Aug-19	1861	7173	0	7868	<b>16,902</b>	1230	5154	1446
Sep-19	2853	8569	0	807	<b>12,229</b>	1865	6593	1171
Oct-19	6038	9632	0	0	<b>15,670</b>	738	10546	1471

# — AMBIENT AIR QUALITY



## AMBIENT AIR QUALITY

- Continue to actively participate in LICA and the Air Quality Monitoring Program Network as per the Lindbergh SAGD EPEA Approval 1581-02-03
- We are compliant with the Joint Oilsands Monitoring (JOSM) requirements

# ENVIRONMENTAL ISSUES







## ENVIRONMENT (EPEA 1581-02-03)

### EPEA Update:

- Wetland and Waterbody Monitoring Program Proposal is now fully approved.
- Amended Wildlife Mitigation & Monitoring Program is now fully approved (December 2019).
- Project Level Conservation and Reclamation Closure Plan submitted October 2019. Currently in review by AER.

# COMPLIANCE



## COMPLIANCE

### Non-Compliances

- July 2019 – Non-compliance – Improper dike/spill mitigation measures for temporary dikes containing a brine solution. The tanks were removed to establish compliance.
- There were no other non-compliance events and no self-disclosures in 2019.

# FUTURE PLANS



## FUTURE PLANS

- Continuous incremental expansion of the CPF to 40,000 bbl/d
- Implementation of solvent assisted SAGD to improve efficiency and recovery
- Continue implementation of NCG injection with steam to improve efficiency and recovery
- Increased Cogeneration of steam and electricity

## Pengrowth Energy Corporation

1600, 222 – 3<sup>rd</sup> Avenue SW  
Calgary, Alberta, Canada T2P 0B4

Telephone: 403.233.0224  
Toll Free: 1.800.223.4122  
Facsimile: 403.265.6251

## Investor Relations

Toll-free: 1.855.336.8814  
Email: [investorrelations@pengrowth.com](mailto:investorrelations@pengrowth.com)  
Website: [www.pengrowth.com](http://www.pengrowth.com)

